
Proposed Subdivision -
Hereford Hill
Stages 15 & 16,
Site Classification

Pasture Street and
Dairyman Drive,
Lochinvar

NEW17P-0054F-AB
7 June 2022



7 June 2022

McCloy Project Management Pty Ltd
Suite 1, Level 3, 426 King Street
NEWCASTLE WEST NSW 2309

Attention: Mr Rylan Gibson

Dear Sir,


**RE: PROPOSED SUBDIVISION – HEREFORD HILL – STAGES 15 & 16
PASTURE STREET AND DAIRYMAN DRIVE, LOCHINVAR
SITE CLASSIFICATION (LOTS 1501 TO 1514 AND 1601 TO 1630)**

Please find enclosed our geotechnical report for the proposed residential subdivision of Hereford Hill, Stages 15 and 16, located at Pasture Street and Dairyman Drive, Lochinvar.

The report includes recommendations for Site Classification in accordance with AS2870-2011, "*Residential Slabs and Footings*".

If you have any questions regarding this report, please do not hesitate to contact Ben Edwards, Shannon Kelly, or the undersigned.

For and on behalf of Qualtest Laboratory (NSW) Pty Ltd



Jason Lee
Principal Geotechnical Engineer

Table of Contents:

1.0	Introduction	1
2.0	Desktop Study	1
3.0	Field Work	1
4.0	Site Description	2
4.1	Site Regrade Works.....	2
4.2	Surface Conditions	3
4.3	Subsurface Conditions.....	4
5.0	Laboratory Testing	10
6.0	Site Classification to AS2870-2011	12
7.0	Limitations.....	13

Attachments:

- Figure AB1: Site Plan and Approximate Test Locations
- Appendix A: Results of Field Investigations
- Appendix B: Results of Laboratory Testing
- Appendix C: CSIRO Sheet BTF 18

1.0 Introduction

Qualtest Laboratory NSW Pty Ltd (Qualtest) is pleased to present this geotechnical site classification report to McCloy Project Management Pty Ltd (McCloy), for Stages 15 & 16 of the proposed subdivision located at Pasture Street and Dairyman Drive, Lochinvar.

Based on the Brief and Plans of the subdivision provided in an email dated 11 April 2022 from McCloy, Stages 15 and 16 are understood to include 44 residential allotments (Lots 1501 to 1514 and Lots 1601 to 1630), as shown in Figure AB1.

The scope of work included providing site classification with respect to reactive soils, in accordance with the requirements of AS2870-2011 'Residential Slabs and Footings', for Stages 15 & 16 following completion of site regrade works.

This report presents the results of the field work investigations and laboratory testing, and provides recommendations for the scope outlined above.

2.0 Desktop Study

The scope of work has included a review of the following reports completed by Qualtest:

- Level 1 Site Regrade Assessment Report, 'Proposed Subdivision of Hereford Hill – Stage 11, 12, 18, & 19, Lochinvar', (Report Reference: NEW20P-0146B-AA, dated 7 July, 2021);
- Preliminary Geotechnical Assessment, 'Proposed Subdivision – Hereford Hill DA2 Area (Stages 13, 14 & 15), Lots 2 & 3, DP1218389, New England Highway, Lochinvar', (Report Reference: NEW17P-0054D-AB, dated 12 July 2021);
- Geotechnical Assessment, 'Proposed Subdivision – Hereford Hill DA2 Area – Stages 11, 12, & 16, New England Highway, Lochinvar', (Report Reference: NEW17P-0054C-AC.Rev1, dated 12 July 2021);
- Site Classification, 'Proposed Subdivision – Hereford Hill – Stages 13 and 14, Eloura Street and Drover Drive, Lochinvar', (Report Reference: NEW17P-0054D-AD, dated 28 January 2022); and,
- Site Classification, 'Proposed Subdivision – Hereford Hill – Stages 11 and 12, Gregory Road and Silo Street, Lochinvar', (Report Reference: NEW17P-0054C-AD, dated 3 November 2021).

This report includes selected results from the reports referenced above, to supplement information collected during the current investigations where applicable. Reference should be made to the reports outlined above for further details of site conditions, field work and laboratory testing conducted, site supervision, and testing carried out.

3.0 Field Work

The field work investigations were carried out on 26 and 27 April 2022 and comprised of:

- DBYD search and visual check of proposed test locations for the presence of underground services;
- Site walkover to make observations of surface features at the property and in the immediate surrounding area;

- Drilling of twenty-four (24 no.) boreholes (BH1501 to BH1508, and BH1601 to BH1616) using a 2.7 tonne excavator equipped with a 300mm diameter auger. Boreholes were terminated at depths of between 1.00m and 2.00m, with undisturbed samples (U50 tubes) taken for subsequent laboratory testing; and,
- Boreholes were backfilled with the excavation spoil and compacted using the excavator auger and tracks.

Investigations were carried out by an experienced Geotechnical Engineer from Qualtest who located the boreholes, carried out the testing and sampling, produced field logs of the boreholes, and made observations of the site surface conditions.

Approximate borehole locations are shown on the attached Figure AB1. Boreholes were located in the field by handheld GPS and relative to existing site features including topographic features, lot boundaries, existing developments and trees.

Engineering logs of the boreholes are presented in Appendix A.

4.0 Site Description

4.1 Site Regrade Works

Site re-grading for the Stage 16 bulk earthworks, (which was previously referred to as being within Stages 11, 12, 18 & 19 in 2021 prior to renumbering of Lots / Stages) was conducted between 14 April 2021 and 8 June 2021. Re-grade works included filling of existing site dam and drainage channels, cutting and filling within Stages 11, 12, 18 & 19, along with cut / fill works performed for the foundation of a proposed keyway, with the construction of a permanent Detention Basin adjacent to New England Highway.

Refer to attached Figure AB1 for the approximate extent of lot re-grade works for this stage of the development.

Prior to filling, re-grade areas were stripped of topsoil and unsuitable material to expose the suitable natural foundation profile. Preparation works were then performed, which consisted of tining, re-conditioning and re-compaction of the stripped surface. Following preparation works, a proof roll assessment was then performed prior to filling with approved site fill to design finish levels.

Filling was performed using site stockpiled material won from excavations cut from around the site. The fill material could generally be described as mixtures of Residual (CI-CH) Sandy CLAY, medium to high plasticity, brown / red in colour, with fine to coarse grained Sand and Gravel.

The approximate depth of fill placed ranged in the order of 0.1m to about 3.6m, with the deepest areas within an existing dam within Lots 1619 to 1621.

The fill was compacted in maximum lifts of 0.3m thickness. Any unsuitable or deleterious material within the fill was removed by hand or mechanical means prior to final compaction of the material.

As the geotechnical testing authority engaged for the project, we state that the re-grading works performed within Stage 16 (as shown on attached Figure AB2), was carried out to Level 1 criteria as defined in Clause 8.2 – Section 8, of AS3798-2007, “*Guidelines on Earthworks for Commercial and Residential Developments*”.

The recommendations of this report are based on the understanding that any existing lot re-grade works are limited to the controlled earthworks supervised by Qualtest, and placement of low reactivity topsoil material such that total depth of topsoil and uncontrolled fill does not exceed 0.4m. Qualtest should be informed without delay if additional earthworks are known to have been carried out.

During field investigations undertaken on 26 and 27 April 2022, there was noted to be fill stockpiles on a number of lots within Stages 15 & 16. The lots have been classified based on the understanding that these stockpiles are to be removed prior to construction of residential footings.

4.2 Surface Conditions

The site comprises Stages 15 and 16 of the Hereford Hill residential subdivision, located at Pasture Street and Dairyman Drive, respectively, as shown on Figure AB1 attached.

The site is located within a region of gently undulating topography, and is bounded by existing and futures stages of the proposed subdivision including Stage 1 and Stages 11 to 14 to the east and south, New England Highway to the north, an existing basin to the northwest of the site, and rural dwellings and future subdivision to the west.

Selected photographs of the site taken on the days of the site investigation are shown below.



Photograph 1: From near BH1502 (Lot 1503), facing south.



Photograph 2: From near BH1502 (Lot 1502), facing north.



Photograph 3: From near BH1505 (Lot 1507), facing northeast.



Photograph 4: From near BH1505 (Lot 1507), facing east.



Photograph 5: From near BH1501 (Lot 1610), facing north.



Photograph 6: From near BH1501 (Lot 1501), facing south.



Photograph 7: Near BH1601 (Lot 1601), facing west.



Photograph 8: Near BH1601 (Lot 1601), facing north.



Photograph 9: From near BH1615 (Lot 1628), facing southwest.



Photograph 10: From near BH1615 (Lot 1628), facing west.



Photograph 11: Near BH1610 (Lot 1619), facing west.



Photograph 12: Near BH1610 (Lot 1619), facing north. Showing existing basin and overflow area located in the northeast corner of site.



Photograph 13: From Lot 1630, facing north.



Photograph 14: From Lot 1630, facing south.

4.3 Subsurface Conditions

Reference to the 1:100,000 Cessnock Regional Geology Series Sheet 9132 indicates the site to be underlain by the Lochinvar Formation of the Dalwood Group, which is characterised by lithic feldspathic sandstone, siltstone, shale, tuff, basalt flows and erratics.

Table 1 presents a summary of the typical soil / rock types encountered at the borehole locations during the field investigations, divided into representative geotechnical units.

Table 2 contains a summary of the distribution of the above geotechnical units at the borehole locations.

TABLE 1 – SUMMARY OF GEOTECHNICAL UNITS AND SOIL TYPES

Unit	Soil Type	Description
1A	Fill – Topsoil	Sandy CLAY - medium to high plasticity, grey-brown, fine to medium grained sand, trace fine grained angular gravel, root affected.
1B	Fill – Controlled	CLAY - medium to high plasticity, brown with some grey-brown, trace orange, trace fine to coarse grained sand, trace fine to medium grained angular gravel.
2	Topsoil	Sandy CLAY - medium to high plasticity, brown, fine grained sand, trace rootlets.
3	Colluvium	CLAY, Sandy CLAY - medium to high plasticity, grey with some brown.
4	Residual Soil	<p>CLAY - medium to high plasticity, red-brown / brown, trace fine to coarse grained sand, trace pockets of Gravelly SAND.</p> <p>Sandy CLAY – generally medium plasticity, pale brown to pale grey-brown trace pale orange, fine to coarse grained (mostly fine grained) sand, trace fine grained sub-angular gravel in places.</p> <p>Gravelly Sandy CLAY - low to medium plasticity, pale grey with some brown, fine to coarse grained sand, fine grained angular gravel.</p> <p>Clayey Sandy GRAVEL - fine to medium grained angular, grey to brown with some orange, fine to coarse grained sand, fines of medium plasticity.</p> <p>Borderline Extremely Weathered Rock in places.</p>
5	Extremely Weathered (XW) Rock with soil properties	<p>Andesite; breaks down into Gravelly Sandy CLAY - medium plasticity, pale brown to pale grey, with some pockets of CLAY in places.</p> <p>Andesite; breaks down into Clayey Sandy GRAVEL - fine to medium grained angular, grey to brown with some orange, fine to coarse grained sand, fines of medium plasticity.</p> <p>Andesite; breaks down into Gravelly SAND - fine to coarse grained, pale grey and pale brown, fine to medium grained angular gravel, with some fines of low to medium plasticity.</p>
6	Highly Weathered (HW) to Moderately Weathered (MW) Rock	ANDESITE - brown to dark brown and dark grey, varying rock strength estimated between low and high strength.

TABLE 2 – SUMMARY OF GEOTECHNICAL UNITS ENCOUNTERED AT EACH TEST LOCATION

Location	Unit 1A	Unit 1B	Unit 2	Unit 3	Unit 4	Unit 5	Unit 6
	Fill – Topsoil	Fill – Controlled	Topsoil	Colluvium	Residual Soil	XW Rock	HW Rock
Depth in metres (m)							
BH1501	-	-	0.00 - 0.10	-	0.10 - 2.00	-	-
BH1502	-	-	0.00 - 0.10	-	0.10 - 2.00	-	-
BH1503	-	-	0.00 - 0.10	0.10 - 0.25	0.25 - 1.30	1.30 - 1.70	1.70 - 2.00 [^]
BH1504	-	-	0.00 - 0.10	-	0.10 - 1.70	1.70 - 2.00 [^]	-
BH1505	-	-	0.00 - 0.10	-	0.10 - 0.40	0.40 - 0.90	0.90 - 1.00 [*]
BH1506	-	-	0.00 - 0.10	-	0.10 - 0.60	0.60 - 2.00 [^]	-
BH1507	-	-	0.00 - 0.10	-	0.10 - 2.00 [^]	-	-
BH1508	-	-	0.00 - 0.10	-	0.10 - 1.50	-	1.50 - 1.60 [*]
BH1601	-	-	0.00 - 0.15	0.15 - 0.35	0.35 - 1.70	1.70 - 1.80 [^]	-
BH1602	-	-	0.00 - 0.20	-	0.20 - 2.00	-	-
BH1603	0.00 - 0.20	0.20 - 1.40	-	-	1.40 - 2.00	-	-
BH1604	0.00 - 0.10	0.10 - 1.50	-	-	1.50 - 2.00	-	-
BH1605	0.00 - 0.10	0.10 - 1.50	-	-	1.50 - 2.00	-	-
BH1606	-	-	0.00 - 0.10	-	0.10 - 2.00	-	-
BH1607	-	-	0.00 - 0.10	-	0.10 - 2.00	-	-

Location	Unit 1A Fill – Topsoil	Unit 1B Fill – Controlled	Unit 2 Topsoil	Unit 3 Colluvium	Unit 4 Residual Soil	Unit 5 XW Rock	Unit 6 HW Rock
	Depth in metres (m)						
BH1608	-	-	0.00 - 0.10	-	0.10 - 2.00	-	-
BH1609	-	-	0.00 - 0.10	0.10 - 0.30	0.30 - 2.00	-	-
BH1610	0.00 - 0.10	0.10 - 2.00	-	-	-	-	-
BH1611	0.00 - 0.10	0.10 - 2.00	-	-	-	-	-
BH1612	0.00 - 0.15	0.15 - 1.80	-	1.80 - 2.00	-	-	-
BH1613	0.00 - 0.10	0.10 - 1.50	-	-	-	1.50 - 2.00 [^]	-
BH1614	0.00 - 0.20	0.20 - 1.00	-	-	1.00 - 2.00	-	-
BH1615	0.00 - 0.10	0.10 - 0.30	-	-	0.30 - 1.00	1.00 - 2.00 [^]	-
BH1616	-	-	0.00 - 0.10	-	0.10 - 1.40	1.40 - 2.00	-
Previous Investigation (Ref. NEW17P-0054D-AD, dated 28 January 2022)							
BH1305	-	-	0.00 - 0.10	-	0.10 - 0.70	0.70 - 2.30	-
BH1306	-	-	0.00 - 0.10	-	0.10 - 1.30	1.30 - 2.30	-
BH1405	-	-	0.00 - 0.10	-	0.10 - 1.50	1.50 - 2.30	-
BH1406	-	-	0.00 - 0.10	-	0.10 - 1.60	1.60 - 2.30	-
Previous Geotechnical Investigation (Ref: NEW17P-0054C-AD, dated 3 November 2021)							
BH1101	0.00 - 0.40	-	-	-	0.40 - 1.20	1.20 - 2.00	-

Location	Unit 1A Fill – Topsoil	Unit 1B Fill – Controlled	Unit 2 Topsoil	Unit 3 Colluvium	Unit 4 Residual Soil	Unit 5 XW Rock	Unit 6 HW Rock
	Depth in metres (m)						
BH1102	0.00 - 0.40	-	-	-	0.40 - 2.00	-	-
BH1103	-	0.00 - 0.50	-	-	0.50 - 0.90	0.90 - 2.00	-
BH1104	0.00 - 0.10	0.10 - 0.70	-	-	0.70 - 1.80	1.80 - 2.00	-
BH1105	0.00 - 0.10	0.10 - 1.60	-	-	1.60 - 2.50	-	-
BH1106	0.00 - 0.15	0.15 - 1.50	-	-	1.50 - 2.00	-	-
BH1107	-	-	0.00 – 0.20	-	0.20 - 1.80	1.80 - 2.00	-
BH1204	-	-	-	-	0.00 - 0.80	0.80 - 2.00	-
BH1205	-	-	-	-	0.00 - 0.75	0.75 - 2.00	-
Previous Geotechnical Investigation (Ref: NEW17P-0054D-AB, dated 12 July 2021)							
BHQ05	-	-	0.00 - 0.10	0.10 - 1.30	1.30 - 2.00 [^]	-	-
BHQ06	-	-	0.00 - 0.10	0.10 - 1.50	1.50 - 1.90 [^]	-	-
Previous Geotechnical Investigation (Ref: NEW17P-0054C-AC, dated 13 May 2021)							
TPP01	-	-	0.00 - 0.15	-	0.15 - 1.80	-	1.80 - 1.95 [^]
TPP02	-	-	0.00 - 0.10	-	0.10 - 2.00	-	-
TPP03	-	-	0.00 - 0.20	-	0.30 - 1.50	1.50 - 1.95	1.95 - 2.00 [^]
TPP04	0.00 - 0.40	-	-	-	0.40 - 1.60	1.60 - 1.75 [^]	-

Location	Unit 1A	Unit 1B	Unit 2	Unit 3	Unit 4	Unit 5	Unit 6
	Fill – Topsoil	Fill – Controlled	Topsoil	Colluvium	Residual Soil	XW Rock	HW Rock
Depth in metres (m)							
BHP05	-	-	0.00 - 0.15	-	0.15 - 1.00 1.10 - 1.50	1.00 – 1.10 1.50 - 2.00	-
TPP06	-	-	0.00 - 0.15	-	0.15 - 1.20	1.20 - 2.00	-
TPP07	-	-	0.00 - 0.10	-	0.10 - 0.70	0.70 - 1.20	1.20 - 1.60*
BHP08	-	-	0.00 - 0.15	-	0.15 - 1.10	1.10 - 2.00^	-
TPP09	-	-	0.00 - 0.10	-	0.10 - 1.80^	-	-
TPP10	-	-	0.00 - 0.10	-	0.10 - 0.90	0.90 - 1.70^	-
Previous Geotechnical Investigation (Ref: NEW17P-0054A-AA.Rev2, dated 19 August 2020)							
TP126	-	-	0.00 - 0.15	0.15 - 0.25	0.25 - 1.60	1.60 - 1.90^	-
TP127	-	-	0.00 - 0.15	0.15 - 0.35	0.35 - 1.20	1.20 - 1.90	1.90 - 2.00*
Note:	^ = Slow to very slow progress of 2.7 tonne excavator. * = Practical refusal of 2.7 tonne excavator met on Highly Weathered Rock.						

No groundwater levels or inflows were encountered in the boreholes during the limited time that they remained open on the day of the field investigations.

It should be noted that groundwater conditions can vary due to rainfall and other influences including regional groundwater flow, temperature, permeability, recharge areas, surface condition, and subsoil drainage.

5.0 Laboratory Testing

Samples collected during the current field investigations were returned to our NATA accredited Newcastle Laboratory for testing which comprised of:

- (33 no.) Shrink / Swell tests.

Results of the laboratory testing are presented in Appendix B, with a summary of the Shrink/Swell test results presented in Table 3.

Laboratory test results from previous investigations are included where applicable.

TABLE 3 – SUMMARY OF SHRINK / SWELL TESTING RESULTS

Location	Depth (m)	Material Description	I _{ss} (%)
Current Investigation			
BH1501	0.50 – 0.65	(CH) CLAY	4.6
BH1502	0.50 – 0.64	(CH) CLAY	1.1
BH1503	0.60 – 0.85	(CH) CLAY	5.7
BH1504	0.50 – 0.64	(CH) CLAY	4.6
BH1505	0.20 – 0.35	(CH) CLAY	1.4
BH1506	0.35 – 0.60	(CH) CLAY	4.4
BH1507	0.50 – 0.65	(CH) CLAY	4.7
BH1508	0.20 – 0.33	(CH) CLAY	3.4
BH1601	0.50 – 0.70	(CH) CLAY	4.7
BH1602	0.50 – 0.70	(CH) CLAY	4.5
BH1602	1.00 – 1.15	(CL) Gravelly Sandy CLAY	2.8
BH1603	0.40 – 0.52	FILL: (CH) CLAY	2.7
BH1603	1.00 – 1.20	FILL: (CH) CLAY	4.0
BH1604	0.40 – 0.60	FILL: (CH) CLAY	2.6
BH1604	1.00 – 1.15	FILL: (CH) CLAY	3.0
BH1605	0.40 – 0.57	FILL: (CH) CLAY	3.0
BH1605	1.00 – 1.18	FILL: (CH) CLAY	3.8
BH1606	0.50 – 0.63	(CH) CLAY	3.8
BH1607	0.50 – 0.66	(CH) CLAY	3.8
BH1608	0.40 – 0.60	(CH) CLAY	4.1
BH1609	0.60 – 0.75	(CH) CLAY	3.7
BH1610	0.50 – 0.63	FILL: (CH) CLAY	4.5
BH1610	1.00 – 1.20	FILL: (CH) CLAY	2.3

BH1611	0.50 – 0.75	FILL: (CH) CLAY	4.0
BH1611	1.00 – 1.15	FILL: (CH) CLAY	2.1
BH1612	0.40 – 0.55	FILL: (CH) CLAY	2.5
BH1612	1.00 – 1.15	FILL: (CH) CLAY	2.2
BH1613	0.50 – 0.65	FILL: (CH) CLAY	5.6
BH1613	1.00 – 1.15	FILL: (CH) CLAY	4.8
BH1614	0.70 – 0.95	FILL: (CH) CLAY	3.6
BH1615	0.70 – 0.90	(CH) CLAY	4.9
BH1616	0.50 – 0.70	(CH) CLAY	4.4
BH1616	1.00 – 1.20	(CH) CLAY	4.9
Previous Investigation (Ref. NEW17P-0054D-AD, dated 28 January 2022)			
BH1305	0.50 - 0.65	(CH) CLAY	0.6
BH1306	0.60 - 0.90	(CH) CLAY	3.4
BH1405	0.90 - 1.10	(CH) CLAY	3.9
BH1406	0.50 - 0.65	(CH) CLAY	3.8
Previous Geotechnical Investigation (Ref: NEW17P-0054C-AD, dated 3 November 2021)			
BH1101	0.80 - 0.95	(CH) CLAY	3.1
BH1102	0.50 - 0.80	(CH) CLAY	4.6
BH1104	0.50 - 0.60	FILL: (CH) CLAY	3.3
BH1105	0.30 - 0.50	FILL: (CH) Sandy CLAY	2.9
BH1105	1.00 - 1.25	FILL: (CH) Sandy CLAY	3.1
BH1106	1.00 - 1.20	FILL: (CH) CLAY	3.1
BH1107	0.50 - 0.85	(CH) CLAY	3.7
BH1204	0.50 - 0.75	(CH) CLAY	3.4
BH1205	0.50 - 0.70	(CH) CLAY	2.9
Previous Investigation (Ref: NEW17P-0054D-AB, 12 July 2021)			
BHQ06	0.50 – 0.70	(CH) CLAY	3.7
Previous Geotechnical Investigation (Ref: NEW17P-0054C-AC, dated 13 May 2021)			
TPP03	0.60 – 0.80	(CH) CLAY	4.1
TPP04	0.60 – 0.80	(CH) CLAY	3.5
BHP05	0.60 – 0.80	(CH) CLAY	2.5
TPP06	0.50 – 0.65	(CH) CLAY	3.1
BHP08	0.50 – 0.70	(CH) CLAY	2.3
TPP09	0.50 – 0.70	(CH) CLAY	4.4

6.0 Site Classification to AS2870-2011

Based on the results of the field work and laboratory testing, residential lots located within Stages 15 and 16 of the Hereford Hill residential subdivision, are classified in their current condition, in accordance with AS2870-2011 'Residential Slabs and Footings' as shown in Table 4.

TABLE 4 –SITE CLASSIFICATION TO AS2870-2011

Stage	Lot Numbers	Site Classification
15	1501 to 1514	H2
16	1610 to 1616	H2
	1601 to 1609, 1617 to 1630	E
<p>Notes:</p> <p>Localised fill stockpiles and mounded topsoil were present on some lots at the time of the field investigations. Site classifications provided herein are made on the understanding that the fill stockpiles and mounded topsoil will be removed prior to sales / development of the lots, such that remaining topsoil and/or uncontrolled fill depths on lots is less than 0.4m.</p> <p>If any localised areas of topsoil and/or uncontrolled fill of depths greater than 0.4m are encountered during construction, footings should be designed in accordance with engineering principles for Class 'P' sites.</p>		

A characteristic free surface movement in the range of 60mm to 75mm is estimated for the lots classified as **Class 'H2'** in their existing condition.

A characteristic free surface movement in the range of 75mm to 125mm is estimated for the lots classified as **Class 'E'** in their existing condition; although, a characteristic free surface movement in the range of 75mm to 100mm is expected to apply for lots classified as **Class 'E'** with shrink/swell indexes of 4.0% or lower.

The effects of changes to the soil profile by additional cutting and filling and the effects of past and future trees should be considered in selection of the design value for differential movement.

If site re-grading works involving cutting or filling are performed after the date of this assessment the classification may change and further advice should be sought.

Footings for the proposed development should be designed and constructed in accordance with the requirements of AS2870-2011.

The classification presented above assumes that:

- All footings are founded in controlled fill (if applicable) or in the natural clayey soils or rock below all non-controlled fill, topsoil material and root zones, and fill under slab panels meets the requirements of AS2870-2011, in particular, the root zone must be removed prior to the placement of fill materials beneath slabs;
- The performance expectations set out in Appendix B of AS2870-2011 are acceptable, and that site foundation maintenance is undertaken to avoid extremes of wetting and drying;

- Footings are to be founded outside of or below all zones of influence resulting from existing or future service trenches;
- The constructional and architectural requirements for reactive clay sites set out in AS2870-2011 are followed;
- Adherence to the detailing requirement outlined in Section 5 of AS2870-2011 '*Residential Slabs and Footings*' is essential, in particular Section 5.6, '*Additional requirements for Classes M, H1, H2 and E sites*' including architectural restrictions, plumbing and drainage requirements; and,
- Site maintenance complies with the provisions of CSIRO Sheet BTF 18, "*Foundation Maintenance and Footing Performance: A Homeowner's Guide*", a copy of which is attached in Appendix C.

All structural elements on all lots should be supported on footings founded beneath all uncontrolled fill, topsoil, layers of inadequate bearing capacity, soft/loose, wet or other potentially deleterious material.

If any localised areas of uncontrolled fill of depths greater than 0.4m are encountered during construction, footings should be designed in accordance with engineering principles for Class 'P' sites.

7.0 Limitations

The findings presented in the report and used as the basis for recommendations presented herein were obtained using normal, industry accepted geotechnical design practices and standards. To our knowledge, they represent a reasonable interpretation of the general conditions of the site.


The extent of testing associated with this assessment is limited to discrete test locations. It should be noted that subsurface conditions between and away from the test locations may be different to those observed during the field work and used as the basis of the recommendations contained in this report.

If subsurface conditions encountered during construction differ from those given in this report, further advice should be sought without delay.

Data and opinions contained within the report may not be used in other contexts or for any other purposes without prior review and agreement by Qualtest. If this report is reproduced, it must be in full.

If you have any further questions regarding this report, please do not hesitate to contact Ben Edwards, Shannon Kelly or the undersigned.


For and on behalf of Qualtest Laboratory (NSW) Pty Ltd.



Jason Lee
Principal Geotechnical Engineer

FIGURE AB1:

Site Plan and Approximate Test Locations



Client:	McCLOY PROJECT MANAGEMENT PTY LTD	Drawing No:	FIGURE AB1
Project:	PROPOSED RESIDENTIAL SUBDIVISION	Project No:	NEW17P-0054F
Location:	HEREFORD HILL - STAGES 15 & 16, LOCHINVAR	Scale:	AS SHOWN
Title:	SITE PLAN AND APPROXIMATE TEST LOCATIONS	Date:	7/06/2022

APPENDIX A:

Results of Field Investigations



ENGINEERING LOG - BOREHOLE

CLIENT: MCCLOY PROJECT MANAGEMENT PTY LTD
PROJECT: HEREFORD HILL - STAGES 15 & 16
LOCATION: LOCHINVAR

BOREHOLE NO: BH1501
PAGE: 1 OF 1
JOB NO: NEW17P-0054F
LOGGED BY: BE
DATE: 26/4/22

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER ATTACHMENT **SURFACE RL:**
BOREHOLE DIAMETER: 300 mm **DATUM:**

Drilling and Sampling				Material description and profile information					Field Test		Structure and additional observations	
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics, colour, minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type		Result
AD/T	Not Encountered	0.50m		0.5		CH	0.10m TOPSOIL: Sandy CLAY - medium to high plasticity, brown, fine grained sand, trace rootlets.	M > W _p	VS _t	HP	380	TOPSOIL
		U50 0.65m								CLAY - medium to high plasticity, brown.		
				1.0		CH	Brown to red-brown, trace pale grey.			HP	220	
				1.5			Pale grey, with some orange to red-brown.			HP	250	
				2.0			Hole Terminated at 2.00 m			HP	300	

LEGEND:

Water

- Water Level (Date and time shown)
- Water Inflow
- Water Outflow

Strata Changes

- Gradational or transitional strata
- Definitive or distinct strata change

Notes, Samples and Tests

- U₃₀ 50mm Diameter tube sample
- CBR Bulk sample for CBR testing
- E Environmental sample (Glass jar, sealed and chilled on site)
- ASS Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
- B Bulk Sample

Field Tests

- PID Photoionisation detector reading (ppm)
- DCP(x-y) Dynamic penetrometer test (test depth interval shown)
- HP Hand Penetrometer test (UCS kPa)

Consistency		UCS (kPa)	Moisture Condition
VS	Very Soft	<25	D Dry
S	Soft	25 - 50	M Moist
F	Firm	50 - 100	W Wet
St	Stiff	100 - 200	W _p Plastic Limit
VSt	Very Stiff	200 - 400	W _L Liquid Limit
H	Hard	>400	
Fb	Friable		
Density			
V	Very Loose		Density Index <15%
L	Loose		Density Index 15 - 35%
MD	Medium Dense		Density Index 35 - 65%
D	Dense		Density Index 65 - 85%
VD	Very Dense		Density Index 85 - 100%

OT.LIB.1.1.GLB.Log.NON-CORED.BOREHOLE - TEST.PIT.00-TEMPLATE.LOGS.SHEET.GPJ <-DrawingFile> 06/06/2022 16:05 10.02.00.04 Datgel.Lab and In Situ Tool



ENGINEERING LOG - BOREHOLE

CLIENT: MCCLOY PROJECT MANAGEMENT PTY LTD
PROJECT: HEREFORD HILL - STAGES 15 & 16
LOCATION: LOCHINVAR

BOREHOLE NO: BH1502
PAGE: 1 OF 1
JOB NO: NEW17P-0054F
LOGGED BY: BE
DATE: 26/4/22

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER ATTACHMENT **SURFACE RL:**
BOREHOLE DIAMETER: 300 mm **DATUM:**

Drilling and Sampling				Material description and profile information					Field Test		Structure and additional observations		
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics, colour, minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type		Result	
AD/T	Not Encountered			0.50m		CH	TOPSOIL: Sandy CLAY - medium to high plasticity, brown, fine grained sand, trace rootlets.					TOPSOIL	
				0.64m		U50	CLAY - medium to high plasticity, red-brown, trace fine to coarse grained sand, trace pockets of Gravelly SAND.			HP	280	RESIDUAL SOIL	
							CH	With some fine to medium grained sub-rounded gravel.	M > W _p	VSt	HP	320	
											HP	360	
				2.00m			Hole Terminated at 2.00 m						

LEGEND:

Water

- Water Level (Date and time shown)
- Water Inflow
- Water Outflow

Strata Changes

- Gradational or transitional strata
- Definitive or distinct strata change

Notes, Samples and Tests

- U₃₀ 50mm Diameter tube sample
- CBR Bulk sample for CBR testing
- E Environmental sample (Glass jar, sealed and chilled on site)
- ASS Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
- B Bulk Sample

Field Tests

- PID Photoionisation detector reading (ppm)
- DCP(x-y) Dynamic penetrometer test (test depth interval shown)
- HP Hand Penetrometer test (UCS kPa)

Consistency		UCS (kPa)	Moisture Condition	
VS	Very Soft	<25	D	Dry
S	Soft	25 - 50	M	Moist
F	Firm	50 - 100	W	Wet
St	Stiff	100 - 200	W _p	Plastic Limit
VSt	Very Stiff	200 - 400	W _L	Liquid Limit
H	Hard	>400		
Fb	Friable			
Density				
V	Very Loose		Density Index <15%	
L	Loose		Density Index 15 - 35%	
MD	Medium Dense		Density Index 35 - 65%	
D	Dense		Density Index 65 - 85%	
VD	Very Dense		Density Index 85 - 100%	

OT.LIB.1.1.GLB.Log.NON-CORED.BOREHOLE - TEST.PIT.00-TEMPLATE.LOGS.SHEET.GPJ <<DrawingFile>> 06/06/2022 16:06 10.02.00.04 Datgel Lab and in Situ Tool



ENGINEERING LOG - BOREHOLE

CLIENT: MCCLOY PROJECT MANAGEMENT PTY LTD
PROJECT: HEREFORD HILL - STAGES 15 & 16
LOCATION: LOCHINVAR

BOREHOLE NO: BH1503
PAGE: 1 OF 1
JOB NO: NEW17P-0054F
LOGGED BY: BE
DATE: 26/4/22

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER ATTACHMENT **SURFACE RL:**
BOREHOLE DIAMETER: 300 mm **DATUM:**

Drilling and Sampling				Material description and profile information					Field Test		Structure and additional observations	
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics, colour, minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type		Result
AD/T	Not Encountered	U50	0.60m	0.85m		CH	TOPSOIL: Sandy CLAY - medium to high plasticity, brown, fine grained sand, trace rootlets.	M > W _p	St - VSt	HP	220	TOPSOIL
						CH	CLAY - medium to high plasticity, grey with some brown.					COLLUVIUM
						CH	CLAY - medium to high plasticity, pale brown.					RESIDUAL SOIL
						CH	Sandy CLAY - medium plasticity, pale brown to pale grey-brown, trace pale orange, fine grained sand.	M < W _p	H / Fb	HP	250	EXTREMELY WEATHERED ROCK
						CI	Extremely Weathered Andesite with soil properties; breaks down into Gravelly Sandy CLAY - medium plasticity, pale brown to pale grey, fine to coarse grained sand, fine grained angular gravel.					HIGHLY WEATHERED ROCK
						CI	ANDESITE - brown to dark brown and dark grey, estimated low strength.	D				
							Hole Terminated at 2.00 m Slow progress					

LEGEND:
Water
 Water Level (Date and time shown)
 Water Inflow
 Water Outflow
Strata Changes
 Gradational or transitional strata
 Definitive or distinct strata change

Notes, Samples and Tests
U₃₀ 50mm Diameter tube sample
CBR Bulk sample for CBR testing
E Environmental sample (Glass jar, sealed and chilled on site)
ASS Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
B Bulk Sample
Field Tests
PID Photoionisation detector reading (ppm)
DCP(x-y) Dynamic penetrometer test (test depth interval shown)
HP Hand Penetrometer test (UCS kPa)

Consistency		UCS (kPa)	Moisture Condition
VS	Very Soft	<25	D Dry
S	Soft	25 - 50	M Moist
F	Firm	50 - 100	W Wet
St	Stiff	100 - 200	W _p Plastic Limit
VSt	Very Stiff	200 - 400	W _L Liquid Limit
H	Hard	>400	
Fb	Friable		
Density			
V	Very Loose		Density Index <15%
L	Loose		Density Index 15 - 35%
MD	Medium Dense		Density Index 35 - 65%
D	Dense		Density Index 65 - 85%
VD	Very Dense		Density Index 85 - 100%



ENGINEERING LOG - BOREHOLE

CLIENT: MCCLOY PROJECT MANAGEMENT PTY LTD
PROJECT: HEREFORD HILL - STAGES 15 & 16
LOCATION: LOCHINVAR

BOREHOLE NO: BH1504
PAGE: 1 OF 1
JOB NO: NEW17P-0054F
LOGGED BY: BE
DATE: 26/4/22

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER ATTACHMENT **SURFACE RL:**
BOREHOLE DIAMETER: 300 mm **DATUM:**

Drilling and Sampling				Material description and profile information					Field Test		Structure and additional observations					
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics, colour, minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type		Result				
AD/T	Not Encountered	0.50m		0.5		CH	0.10m TOPSOIL: Sandy CLAY - medium to high plasticity, brown to red-brown, fine to coarse grained sand, trace fine grained angular gravel, trace rootlets. CLAY - medium to high plasticity, brown, with grey-brown.	M > W _p	VSt	HP	390	TOPSOIL				
		U50 0.64m											HP	380	RESIDUAL SOIL	
				1.0										HP	300	
				1.5										HP	320	
				1.20m		CI	Sandy CLAY - medium plasticity, pale brown to pale grey-brown, trace pale orange, fine grained sand.	M < W _p	H / Fb			RESIDUAL SOIL / EXTREMELY WEATHERED ROCK				
				1.70m		GC	Extremely Weathered Andesite with soil properties; breaks down into Clayey Sandy GRAVEL - fine to medium grained angular, grey to brown with some orange, fine to coarse grained sand, fines of medium plasticity.	D				EXTREMELY WEATHERED ROCK				
				2.00m			Hole Terminated at 2.00 m Very slow progress									

LEGEND:
Water
 Water Level (Date and time shown)
 Water Inflow
 Water Outflow
Strata Changes
 Gradational or transitional strata
 Definitive or distinct strata change

Notes, Samples and Tests
U₃₀ 50mm Diameter tube sample
CBR Bulk sample for CBR testing
E Environmental sample (Glass jar, sealed and chilled on site)
ASS Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
B Bulk Sample
Field Tests
PID Photoionisation detector reading (ppm)
DCP(x-y) Dynamic penetrometer test (test depth interval shown)
HP Hand Penetrometer test (UCS kPa)

Consistency		UCS (kPa)	Moisture Condition
VS	Very Soft	<25	D Dry
S	Soft	25 - 50	M Moist
F	Firm	50 - 100	W Wet
St	Stiff	100 - 200	W _p Plastic Limit
VSt	Very Stiff	200 - 400	W _L Liquid Limit
H	Hard	>400	
Fb	Friable		
Density			
V	Very Loose		Density Index <15%
L	Loose		Density Index 15 - 35%
MD	Medium Dense		Density Index 35 - 65%
D	Dense		Density Index 65 - 85%
VD	Very Dense		Density Index 85 - 100%



ENGINEERING LOG - BOREHOLE

CLIENT: MCCLOY PROJECT MANAGEMENT PTY LTD
PROJECT: HEREFORD HILL - STAGES 15 & 16
LOCATION: LOCHINVAR

BOREHOLE NO: BH1505
PAGE: 1 OF 1
JOB NO: NEW17P-0054F
LOGGED BY: BE
DATE: 26/4/22

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER ATTACHMENT **SURFACE RL:**
BOREHOLE DIAMETER: 300 mm **DATUM:**

Drilling and Sampling				Material description and profile information					Field Test		Structure and additional observations	
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics, colour, minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type		Result
AD/T	Not Encountered	0.20m		0.10m	CH	CH	TOPSOIL: Sandy CLAY - medium to high plasticity, brown, fine grained sand, trace fine to medium grained angular gravel, root affected.	M > W _p	VSt	HP	320	TOPSOIL
		U50 0.35m		0.40m	CH	CLAY - medium to high plasticity, brown.	RESIDUAL SOIL					
				0.5	GC	GC	Extremely Weathered Andesite with soil properties; breaks down into Clayey Sandy GRAVEL - fine to medium grained angular, pale brown, fine to coarse grained sand, fines of low plasticity.	D - M	H / Fb			EXTREMELY WEATHERED ROCK
				1.0		1.00m		ANDESITE - brown to dark brown and dark grey, estimated high strength, slightly fractured.	D			
							Hole Terminated at 1.00 m Refusal					

OT.LIB.1.1.GLB.Log.NON-CORED.BOREHOLE - TEST.PIT.00-TEMPLATE.LOGS.SHEET.GPJ <-DrawingFile> 06/06/2022 16:06 10.02.00.04 Datgel.Lab and In Situ Tool

LEGEND: Water Water Level (Date and time shown) Water Inflow Water Outflow Strata Changes Gradational or transitional strata Definitive or distinct strata change	Notes, Samples and Tests U ₃₀ 50mm Diameter tube sample CBR Bulk sample for CBR testing E Environmental sample (Glass jar, sealed and chilled on site) ASS Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled) B Bulk Sample	Consistency VS Very Soft S Soft F Firm St Stiff VSt Very Stiff H Hard Fb Friable	UCS (kPa) <25 25 - 50 50 - 100 100 - 200 200 - 400 >400	Moisture Condition D Dry M Moist W Wet W _p Plastic Limit W _L Liquid Limit
	Field Tests PID Photoionisation detector reading (ppm) DCP(x-y) Dynamic penetrometer test (test depth interval shown) HP Hand Penetrometer test (UCS kPa)	Density V Very Loose L Loose MD Medium Dense D Dense VD Very Dense	Density Index <15% Density Index 15 - 35% Density Index 35 - 65% Density Index 65 - 85% Density Index 85 - 100%	



ENGINEERING LOG - BOREHOLE

CLIENT: MCCLOY PROJECT MANAGEMENT PTY LTD
PROJECT: HEREFORD HILL - STAGES 15 & 16
LOCATION: LOCHINVAR

BOREHOLE NO: BH1506
PAGE: 1 OF 1
JOB NO: NEW17P-0054F
LOGGED BY: BE
DATE: 26/4/22

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER ATTACHMENT **SURFACE RL:**
BOREHOLE DIAMETER: 300 mm **DATUM:**

Drilling and Sampling				Material description and profile information					Field Test		Structure and additional observations	
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics, colour, minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type		Result
AD/T	Not Encountered	0.35m		0.10m	CH	CH	TOPSOIL: Sandy CLAY - medium to high plasticity, brown, fine grained sand, trace fine to medium grained angular gravel, root affected.	M > W _p	VSt	HP	280	TOPSOIL
		U50		0.5	CH	CH	CLAY - medium to high plasticity, brown.			HP	300	RESIDUAL SOIL
		0.60m		0.60m	GC	GC	Extremely Weathered Andesite with soil properties; breaks down into Clayey Sandy GRAVEL - fine to medium grained angular, pale brown, fine to coarse grained sand, fines of low plasticity, trace pockets of CLAY.	D - M	D			EXTREMELY TO HIGHLY WEATHERED ROCK
		1.0			Gravel portion is fine to coarse grained.							
				1.5								
				2.0			Hole Terminated at 2.00 m Slow progress					

LEGEND:
Water
 Water Level (Date and time shown)
 Water Inflow
 Water Outflow
Strata Changes
 Gradational or transitional strata
 Definitive or distinct strata change

Notes, Samples and Tests
U₃₀ 50mm Diameter tube sample
CBR Bulk sample for CBR testing
E Environmental sample (Glass jar, sealed and chilled on site)
ASS Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
B Bulk Sample
Field Tests
PID Photoionisation detector reading (ppm)
DCP(x-y) Dynamic penetrometer test (test depth interval shown)
HP Hand Penetrometer test (UCS kPa)

Consistency		UCS (kPa)	Moisture Condition
VS	Very Soft	<25	D Dry
S	Soft	25 - 50	M Moist
F	Firm	50 - 100	W Wet
St	Stiff	100 - 200	W _p Plastic Limit
VSt	Very Stiff	200 - 400	W _L Liquid Limit
H	Hard	>400	
Fb	Friable		
Density			
V	Very Loose		Density Index <15%
L	Loose		Density Index 15 - 35%
MD	Medium Dense		Density Index 35 - 65%
D	Dense		Density Index 65 - 85%
VD	Very Dense		Density Index 85 - 100%



ENGINEERING LOG - BOREHOLE

CLIENT: MCCLOY PROJECT MANAGEMENT PTY LTD
PROJECT: HEREFORD HILL - STAGES 15 & 16
LOCATION: LOCHINVAR

BOREHOLE NO: BH1507
PAGE: 1 OF 1
JOB NO: NEW17P-0054F
LOGGED BY: BE
DATE: 26/4/22

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER ATTACHMENT **SURFACE RL:**
BOREHOLE DIAMETER: 300 mm **DATUM:**

Drilling and Sampling				Material description and profile information					Field Test		Structure and additional observations	
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics, colour, minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type		Result
AD/T	Not Encountered	U50		0.50m		CH	TOPSOIL: Sandy CLAY - medium to high plasticity, brown, fine grained sand, trace fine to medium grained angular gravel, root affected. CLAY - medium to high plasticity, brown.	M > W _p	VSt	HP	280	TOPSOIL
				0.65m								
				1.0		CL	Gravelly Sandy CLAY - low to medium plasticity, pale grey with some brown, fine to coarse grained sand, fine grained angular gravel.	M < W _p	VSt / Fb			
				2.0			Hole Terminated at 2.00 m Slow progress					

LEGEND:
Water
 Water Level (Date and time shown)
 Water Inflow
 Water Outflow
Strata Changes
 Gradational or transitional strata
 Definitive or distinct strata change

Notes, Samples and Tests
U₅₀ 50mm Diameter tube sample
CBR Bulk sample for CBR testing
E Environmental sample (Glass jar, sealed and chilled on site)
ASS Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
B Bulk Sample
Field Tests
PID Photoionisation detector reading (ppm)
DCP(x-y) Dynamic penetrometer test (test depth interval shown)
HP Hand Penetrometer test (UCS kPa)

Consistency		UCS (kPa)	Moisture Condition	
VS	Very Soft	<25	D	Dry
S	Soft	25 - 50	M	Moist
F	Firm	50 - 100	W	Wet
St	Stiff	100 - 200	W _p	Plastic Limit
VSt	Very Stiff	200 - 400	W _L	Liquid Limit
H	Hard	>400		
Fb	Friable			
Density				
V	Very Loose		Density Index <15%	
L	Loose		Density Index 15 - 35%	
MD	Medium Dense		Density Index 35 - 65%	
D	Dense		Density Index 65 - 85%	
VD	Very Dense		Density Index 85 - 100%	



ENGINEERING LOG - BOREHOLE

CLIENT: MCCLOY PROJECT MANAGEMENT PTY LTD
PROJECT: HEREFORD HILL - STAGES 15 & 16
LOCATION: LOCHINVAR

BOREHOLE NO: BH1508
PAGE: 1 OF 1
JOB NO: NEW17P-0054F
LOGGED BY: BE
DATE: 26/4/22

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER ATTACHMENT **SURFACE RL:**
BOREHOLE DIAMETER: 300 mm **DATUM:**

Drilling and Sampling				Material description and profile information					Field Test		Structure and additional observations		
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics, colour, minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type		Result	
AD/T	Not Encountered	0.20m				CH	TOPSOIL: Sandy CLAY - medium to high plasticity, brown, fine grained sand, trace rootlets.	M > W _p	VSt	HP	350	TOPSOIL	
		U50 0.33m				CH	CLAY - medium to high plasticity, brown.					RESIDUAL SOIL	
				0.5			CL	Gravelly Sandy CLAY - low to medium plasticity, brown, fine to coarse grained sand, fine grained angular gravel.	M < W _p	H / Fb			
				1.0			CL						
				1.5		D	ANDESITE - brown to dark brown and dark grey, estimated high strength, slightly fractured.					HIGHLY TO MODERATELY WEATHERED ROCK	
				1.60m			Hole Terminated at 1.60 m Refusal						
				2.0									

LEGEND:
Water
 Water Level (Date and time shown)
 Water Inflow
 Water Outflow
Strata Changes
 Gradational or transitional strata
 Definitive or distinct strata change

Notes, Samples and Tests
U₃₀ 50mm Diameter tube sample
CBR Bulk sample for CBR testing
E Environmental sample (Glass jar, sealed and chilled on site)
ASS Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
B Bulk Sample
Field Tests
PID Photoionisation detector reading (ppm)
DCP(x-y) Dynamic penetrometer test (test depth interval shown)
HP Hand Penetrometer test (UCS kPa)

Consistency		UCS (kPa)	Moisture Condition
VS	Very Soft	<25	D Dry
S	Soft	25 - 50	M Moist
F	Firm	50 - 100	W Wet
St	Stiff	100 - 200	W _p Plastic Limit
VSt	Very Stiff	200 - 400	W _L Liquid Limit
H	Hard	>400	
Fb	Friable		
Density			
V	Very Loose		Density Index <15%
L	Loose		Density Index 15 - 35%
MD	Medium Dense		Density Index 35 - 65%
D	Dense		Density Index 65 - 85%
VD	Very Dense		Density Index 85 - 100%



ENGINEERING LOG - BOREHOLE

CLIENT: MCCLOY PROJECT MANAGEMENT PTY LTD
PROJECT: HEREFORD HILL - STAGES 15 & 16
LOCATION: LOCHINVAR

BOREHOLE NO: BH1601
PAGE: 1 OF 1
JOB NO: NEW17P-0054F
LOGGED BY: BE
DATE: 26/4/22

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER ATTACHMENT **SURFACE RL:**
BOREHOLE DIAMETER: 300 mm **DATUM:**

Drilling and Sampling				Material description and profile information					Field Test		Structure and additional observations		
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics, colour, minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type		Result	
AD/T	Not Encountered	U50	0.50m	0.5		CH	TOPSOIL: Sandy CLAY - medium to high plasticity, brown, fine grained sand, trace rootlets.	M > W _p	VSt	HP	380	TOPSOIL	
						CH	Sandy CLAY - medium to high plasticity, dark grey-brown, fine to coarse grained sand, trace fine to medium grained angular gravel.					COLLUVIUM	
						CH	CLAY - medium to high plasticity, brown.					RESIDUAL SOIL	
						CH						HP	300
						CH						HP	350
						CH						HP	220
						CL	CLAY - medium to high plasticity, pale grey to pale brown, with Gravelly SAND pockets.						
CL	Gravelly Sandy CLAY - low to medium plasticity, pale grey, with some brown, fine to coarse grained sand.												
						CI	Extremely Weathered Andesite with soil properties; breaks down into Gravelly Sandy CLAY - medium plasticity, pale brown to pale grey, fine to coarse grained sand, fine grained angular gravel.					EXTREMELY WEATHERED ROCK	
				2.0			Hole Terminated at 1.80 m Very slow progress						

LEGEND:
Water
 Water Level (Date and time shown)
 Water Inflow
 Water Outflow
Strata Changes
 Gradational or transitional strata
 Definitive or distinct strata change

Notes, Samples and Tests
U₃₀ 50mm Diameter tube sample
CBR Bulk sample for CBR testing
E Environmental sample (Glass jar, sealed and chilled on site)
ASS Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
B Bulk Sample
Field Tests
PID Photoionisation detector reading (ppm)
DCP(x-y) Dynamic penetrometer test (test depth interval shown)
HP Hand Penetrometer test (UCS kPa)

Consistency	UCS (kPa)	Moisture Condition
VS Very Soft	<25	D Dry
S Soft	25 - 50	M Moist
F Firm	50 - 100	W Wet
St Stiff	100 - 200	W _p Plastic Limit
VSt Very Stiff	200 - 400	W _L Liquid Limit
H Hard	>400	
Fb Friable		
Density	V Very Loose	Density Index <15%
L Loose	MD Medium Dense	Density Index 15 - 35%
D Dense		Density Index 35 - 65%
VD Very Dense		Density Index 65 - 85%
		Density Index 85 - 100%



ENGINEERING LOG - BOREHOLE

CLIENT: MCCLOY PROJECT MANAGEMENT PTY LTD
PROJECT: HEREFORD HILL - STAGES 15 & 16
LOCATION: LOCHINVAR

BOREHOLE NO: BH1602
PAGE: 1 OF 1
JOB NO: NEW17P-0054F
LOGGED BY: BE
DATE: 26/4/22

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER ATTACHMENT **SURFACE RL:**
BOREHOLE DIAMETER: 300 mm **DATUM:**

Drilling and Sampling				Material description and profile information					Field Test		Structure and additional observations	
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics, colour, minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type		Result
AD/T	Not Encountered	0.50m		0.5		CH	TOPSOIL: Sandy CLAY - medium to high plasticity, brown, fine grained sand, trace rootlets.	M > w _p	VSt	HP	220	TOPSOIL
		U50		0.70m		CH	CLAY - medium to high plasticity, brown, trace fine to coarse grained sand, trace fine grained angular gravel.			HP	240	RESIDUAL SOIL
		U50		1.00m	1.0	CL	Gravelly Sandy CLAY - low to medium plasticity, pale grey with some brown, fine to coarse grained sand, fine grained angular gravel.	M < w _p	Fb / H	HP	240	
		U50		1.15m	2.0	2.00m	Hole Terminated at 2.00 m					

LEGEND:

Water

- Water Level (Date and time shown)
- Water Inflow
- Water Outflow

Strata Changes

- Gradational or transitional strata
- Definitive or distinct strata change

Notes, Samples and Tests

- U₃₀ 50mm Diameter tube sample
- CBR Bulk sample for CBR testing
- E Environmental sample (Glass jar, sealed and chilled on site)
- ASS Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
- B Bulk Sample

Field Tests

- PID Photoionisation detector reading (ppm)
- DCP(x-y) Dynamic penetrometer test (test depth interval shown)
- HP Hand Penetrometer test (UCS kPa)

Consistency		UCS (kPa)	Moisture Condition
VS	Very Soft	<25	D Dry
S	Soft	25 - 50	M Moist
F	Firm	50 - 100	W Wet
St	Stiff	100 - 200	W _p Plastic Limit
VSt	Very Stiff	200 - 400	W _L Liquid Limit
H	Hard	>400	
Fb	Friable		
Density			
V	Very Loose		Density Index <15%
L	Loose		Density Index 15 - 35%
MD	Medium Dense		Density Index 35 - 65%
D	Dense		Density Index 65 - 85%
VD	Very Dense		Density Index 85 - 100%

OT.LIB.1.1.GLB.Log.NON-CORED.BOREHOLE - TEST.PIT.00-TEMPLATE.LOGS.SHEET.GPJ <<DrawingFile>>_06/06/2022_16:06_10.02.00.04_Datgel.Lab.and.in.Sku.Tool



ENGINEERING LOG - BOREHOLE

CLIENT: MCCLOY PROJECT MANAGEMENT PTY LTD
PROJECT: HEREFORD HILL - STAGES 15 & 16
LOCATION: LOCHINVAR

BOREHOLE NO: BH1603
PAGE: 1 OF 1
JOB NO: NEW17P-0054F
LOGGED BY: BE
DATE: 26/4/22

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER ATTACHMENT **SURFACE RL:**
BOREHOLE DIAMETER: 300 mm **DATUM:**

Drilling and Sampling				Material description and profile information					Field Test		Structure and additional observations		
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics, colour, minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type		Result	
AD/T	Not Encountered	0.40m				CH	FILL-TOPSOIL: Sandy CLAY - medium to high plasticity, grey-brown, fine to medium grained sand, trace fine grained angular gravel, root affected.	M > W _p	VSt	HP		FILL - TOPSOIL	
		U50 0.52m		0.20m			FILL: CLAY - medium to high plasticity, brown with some grey-brown trace orange, trace fine grained sand, trace fine to medium grained angular gravel.					250	FILL - CONTROLLED
				0.5								260	
		1.00m		1.0								220	
		U50 1.20m		1.40m			CLAY - medium to high plasticity, brown.					330	RESIDUAL SOIL
				1.70m		CL	Gravelly Sandy CLAY - low to medium plasticity, pale grey with some brown, fine to coarse grained sand, fine grained angular gravel.	M < W _p	H / Fb				
				2.00m			Hole Terminated at 2.00 m						

LEGEND:
Water
 Water Level (Date and time shown)
 Water Inflow
 Water Outflow
Strata Changes
 Gradational or transitional strata
 Definitive or distinct strata change

Notes, Samples and Tests
U₃₀ 50mm Diameter tube sample
CBR Bulk sample for CBR testing
E Environmental sample (Glass jar, sealed and chilled on site)
ASS Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
B Bulk Sample
Field Tests
PID Photoionisation detector reading (ppm)
DCP(x-y) Dynamic penetrometer test (test depth interval shown)
HP Hand Penetrometer test (UCS kPa)

Consistency		UCS (kPa)	Moisture Condition
VS	Very Soft	<25	D Dry
S	Soft	25 - 50	M Moist
F	Firm	50 - 100	W Wet
St	Stiff	100 - 200	W _p Plastic Limit
VSt	Very Stiff	200 - 400	W _L Liquid Limit
H	Hard	>400	
Fb	Friable		
Density			
V	Very Loose		Density Index <15%
L	Loose		Density Index 15 - 35%
MD	Medium Dense		Density Index 35 - 65%
D	Dense		Density Index 65 - 85%
VD	Very Dense		Density Index 85 - 100%

ENGINEERING LOG - BOREHOLE

CLIENT: MCCLOY PROJECT MANAGEMENT PTY LTD
PROJECT: HEREFORD HILL - STAGES 15 & 16
LOCATION: LOCHINVAR

BOREHOLE NO: BH1604
PAGE: 1 OF 1
JOB NO: NEW17P-0054F
LOGGED BY: BE
DATE: 26/4/22

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER ATTACHMENT **SURFACE RL:**
BOREHOLE DIAMETER: 300 mm **DATUM:**

Drilling and Sampling				Material description and profile information					Field Test		Structure and additional observations		
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics, colour, minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type		Result	
AD/T	Not Encountered	0.40m				CH	FILL-TOPSOIL: Sandy CLAY - medium to high plasticity, grey-brown, fine to medium grained sand, trace fine grained angular gravel, root affected. / FILL: CLAY - medium to high plasticity, brown with some grey-brown trace orange, trace fine grained sand, trace fine to medium grained angular gravel.	M > W _p	VSt			FILL - TOPSOIL	
		U50		0.5						HP	360	FILL - CONTROLLED	
		0.60m									HP	380	
		1.00m		1.0						HP	350		
		U50		1.15m									
				1.5		CH	CLAY - medium to high plasticity, brown, trace pale orange.			HP	250	RESIDUAL SOIL	
				2.0		CH	Hole Terminated at 2.00 m			HP	250		

LEGEND:
Water
 Water Level (Date and time shown)
 Water Inflow
 Water Outflow
Strata Changes
 - - - Gradational or transitional strata
 ——— Definitive or distinct strata change

Notes, Samples and Tests
 U₃₀ 50mm Diameter tube sample
 CBR Bulk sample for CBR testing
 E Environmental sample (Glass jar, sealed and chilled on site)
 ASS Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
 B Bulk Sample
Field Tests
 PID Photoionisation detector reading (ppm)
 DCP(x-y) Dynamic penetrometer test (test depth interval shown)
 HP Hand Penetrometer test (UCS kPa)

Consistency		UCS (kPa)	Moisture Condition	
VS	Very Soft	<25	D	Dry
S	Soft	25 - 50	M	Moist
F	Firm	50 - 100	W	Wet
St	Stiff	100 - 200	W _p	Plastic Limit
VSt	Very Stiff	200 - 400	W _L	Liquid Limit
H	Hard	>400		
Fb	Friable			
Density				
V	Very Loose		Density Index <15%	
L	Loose		Density Index 15 - 35%	
MD	Medium Dense		Density Index 35 - 65%	
D	Dense		Density Index 65 - 85%	
VD	Very Dense		Density Index 85 - 100%	



ENGINEERING LOG - BOREHOLE

CLIENT: MCCLOY PROJECT MANAGEMENT PTY LTD
PROJECT: HEREFORD HILL - STAGES 15 & 16
LOCATION: LOCHINVAR

BOREHOLE NO: BH1605
PAGE: 1 OF 1
JOB NO: NEW17P-0054F
LOGGED BY: BE
DATE: 26/4/22

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER ATTACHMENT **SURFACE RL:**
BOREHOLE DIAMETER: 300 mm **DATUM:**

Drilling and Sampling				Material description and profile information					Field Test		Structure and additional observations						
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics, colour, minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type		Result					
AD/T	Not Encountered	0.40m		0.5		CH	FILL-TOPSOIL: Sandy CLAY - medium to high plasticity, grey-brown, fine to medium grained sand, trace fine grained angular gravel, root affected.	M > W _p	VSt	HP	350	FILL - TOPSOIL					
		U50													FILL - CONTROLLED		
		0.57m															
		1.00m		1.0													
		U50															
		1.18m		1.5		CH	FILL: CLAY - medium to high plasticity, brown, with some fine to medium grained angular gravel, trace fine to coarse grained sand.			HP	360						
				1.5		CH	CLAY - medium to high plasticity, brown.			HP	330						
				1.90m		CI	Gravelly Sandy CLAY - medium plasticity, pale grey with some brown, fine to coarse grained sand, fine grained angular gravel.	M ~ W _p		H / Fb							
				2.00m			Hole Terminated at 2.00 m										

LEGEND:

Water

- Water Level (Date and time shown)
- Water Inflow
- Water Outflow

Strata Changes

- Gradational or transitional strata
- Definitive or distinct strata change

Notes, Samples and Tests

- U₃₀ 50mm Diameter tube sample
- CBR Bulk sample for CBR testing
- E Environmental sample (Glass jar, sealed and chilled on site)
- ASS Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
- B Bulk Sample

Field Tests

- PID Photoionisation detector reading (ppm)
- DCP(x-y) Dynamic penetrometer test (test depth interval shown)
- HP Hand Penetrometer test (UCS kPa)

Consistency	UCS (kPa)	Moisture Condition
VS Very Soft	<25	D Dry
S Soft	25 - 50	M Moist
F Firm	50 - 100	W Wet
St Stiff	100 - 200	W _p Plastic Limit
VSt Very Stiff	200 - 400	W _L Liquid Limit
H Hard	>400	
Fb Friable		

Density	Density Index
V Very Loose	<15%
L Loose	15 - 35%
MD Medium Dense	35 - 65%
D Dense	65 - 85%
VD Very Dense	85 - 100%

OT.LIB.1.1.GLB.Log_NON-CORED BOREHOLE - TEST PIT 00-TEMPLATE LOGS SHEET.GPJ <-DrawingFile> 06/06/2022 16:06 10.02.00.04 Datgel Lab and in Situ Tool



ENGINEERING LOG - BOREHOLE

CLIENT: MCCLOY PROJECT MANAGEMENT PTY LTD
PROJECT: HERFORD HILL - STAGES 15 & 16
LOCATION: LOCHINVAR

BOREHOLE NO: BH1606
PAGE: 1 OF 1
JOB NO: NEW17P-0054F
LOGGED BY: BE
DATE: 26/4/22

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER ATTACHMENT **SURFACE RL:**
BOREHOLE DIAMETER: 300 mm **DATUM:**

Drilling and Sampling				Material description and profile information					Field Test		Structure and additional observations	
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics, colour, minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type		Result
AD/T	Not Encountered	U50		0.50m		CH	TOPSOIL: Sandy CLAY - medium to high plasticity, brown, fine grained sand, trace rootlets.	M > W _p	VSt	HP	300	TOPSOIL
		0.63m		0.5		CH	CLAY - medium to high plasticity, brown.			HP	320	RESIDUAL SOIL
				1.0		CL	Gravelly Sandy CLAY - low to medium plasticity, pale brown, fine to coarse grained sand, fine grained angular gravel.			VSt / Fb	280	
				2.0			Hole Terminated at 2.00 m					

OT.LIB.1.1.GLB.Log.NON-CORED.BOREHOLE - TEST.PIT.00-TEMPLATE.LOGS.SHEET.GPJ <<DrawingFile>>_06/06/2022_16:06_10.02.00.04_Datgel.Lab.and.in.Situ.Tool

LEGEND: Water Water Level (Date and time shown) Water Inflow Water Outflow Strata Changes Gradational or transitional strata Definitive or distinct strata change	Notes, Samples and Tests U ₃₀ 50mm Diameter tube sample CBR Bulk sample for CBR testing E Environmental sample (Glass jar, sealed and chilled on site) ASS Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled) B Bulk Sample	Consistency VS Very Soft <25 S Soft 25 - 50 F Firm 50 - 100 St Stiff 100 - 200 VSt Very Stiff 200 - 400 H Hard >400 Fb Friable	UCS (kPa) <25 25 - 50 50 - 100 100 - 200 200 - 400 >400	Moisture Condition D Dry M Moist W Wet W _p Plastic Limit W _L Liquid Limit
	Field Tests PID Photoionisation detector reading (ppm) DCP(x-y) Dynamic penetrometer test (test depth interval shown) HP Hand Penetrometer test (UCS kPa)	Density V Very Loose L Loose MD Medium Dense D Dense VD Very Dense	Density Index <15% Density Index 15 - 35% Density Index 35 - 65% Density Index 65 - 85% Density Index 85 - 100%	



ENGINEERING LOG - BOREHOLE

CLIENT: MCCLOY PROJECT MANAGEMENT PTY LTD
PROJECT: HEREFORD HILL - STAGES 15 & 16
LOCATION: LOCHINVAR

BOREHOLE NO: BH1607
PAGE: 1 OF 1
JOB NO: NEW17P-0054F
LOGGED BY: BE
DATE: 26/4/22

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER ATTACHMENT **SURFACE RL:**
BOREHOLE DIAMETER: 300 mm **DATUM:**

Drilling and Sampling				Material description and profile information					Field Test		Structure and additional observations	
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics, colour, minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type		Result
AD/T	Not Encountered	U50		0.50m		CH	TOPSOIL: Sandy CLAY - medium to high plasticity, brown, fine grained sand, trace rootlets.	M > W _p	VSt	HP	300	TOPSOIL
				0.66m		CH	CLAY - medium to high plasticity, brown.			HP	320	RESIDUAL SOIL
						CL	Gravelly Sandy CLAY - low to medium plasticity, pale grey with some brown, fine to coarse grained sand, fine grained angular gravel.			HP	320	
				2.00m			Hole Terminated at 2.00 m					

OT.LIB.1.1.GLB.Log.NON-CORED.BOREHOLE - TEST.PIT.00-TEMPLATE.LOGS.SHEET.GPJ <-DrawingFile> 06/06/2022.16:06.10.02.00.04.Datgel.Lab.and.in.Sku.Tool

LEGEND: Water Water Level (Date and time shown) Water Inflow Water Outflow Strata Changes Gradational or transitional strata Definitive or distinct strata change	Notes, Samples and Tests U ₃₀ 50mm Diameter tube sample CBR Bulk sample for CBR testing E Environmental sample (Glass jar, sealed and chilled on site) ASS Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled) B Bulk Sample	Consistency VS Very Soft <25 S Soft 25 - 50 F Firm 50 - 100 St Stiff 100 - 200 VSt Very Stiff 200 - 400 H Hard >400 Fb Friable	UCS (kPa) <25 25 - 50 50 - 100 100 - 200 200 - 400 >400	Moisture Condition D Dry M Moist W Wet W _p Plastic Limit W _L Liquid Limit
	Field Tests PID Photoionisation detector reading (ppm) DCP(x-y) Dynamic penetrometer test (test depth interval shown) HP Hand Penetrometer test (UCS kPa)	Density V Very Loose L Loose MD Medium Dense D Dense VD Very Dense	Density Index <15% Density Index 15 - 35% Density Index 35 - 65% Density Index 65 - 85% Density Index 85 - 100%	



ENGINEERING LOG - BOREHOLE

CLIENT: MCCLOY PROJECT MANAGEMENT PTY LTD
PROJECT: HEREFORD HILL - STAGES 15 & 16
LOCATION: LOCHINVAR

BOREHOLE NO: BH1608
PAGE: 1 OF 1
JOB NO: NEW17P-0054F
LOGGED BY: BE
DATE: 26/4/22

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER ATTACHMENT **SURFACE RL:**
BOREHOLE DIAMETER: 300 mm **DATUM:**

Drilling and Sampling				Material description and profile information					Field Test		Structure and additional observations	
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics, colour, minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type		Result
AD/T	Not Encountered	U50		0.10m		CH	TOPSOIL: Sandy CLAY - medium to high plasticity, brown, fine grained sand, trace rootlets.	M > W _p	VSt	HP	230	TOPSOIL
				0.40m		CH	CLAY - medium to high plasticity, brown.					RESIDUAL SOIL
				0.60m		CL	Gravelly Sandy CLAY - low plasticity, pale brown, fine to coarse grained sand, fine grained angular gravel.	M ~ W _p	VSt / Fb	HP	240	RESIDUAL SOIL / EXTREMELY WEATHERED ROCK
				0.90m		GC	Clayey Sandy GRAVEL - fine to medium grained angular, grey to brown with some orange, fine to coarse grained sand, fines of low plasticity.	D - M	D			
			2.00m	2.00m			Hole Terminated at 2.00 m					

OT.LIB.1.1.GLB.Log_NON-CORED BOREHOLE - TEST PIT. 00-TEMPLATE LOGS SHEET.GPJ <<DrawingFile>>_06/06/2022_16:06_10.02.00.04_Datgel.Lab and in Situ Tool

LEGEND: Water Water Level (Date and time shown) Water Inflow Water Outflow Strata Changes Gradational or transitional strata Definitive or distinct strata change	Notes, Samples and Tests U ₃₀ 50mm Diameter tube sample CBR Bulk sample for CBR testing E Environmental sample (Glass jar, sealed and chilled on site) ASS Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled) B Bulk Sample	Consistency VS Very Soft <25 S Soft 25 - 50 F Firm 50 - 100 St Stiff 100 - 200 VSt Very Stiff 200 - 400 H Hard >400 Fb Friable	UCS (kPa) <25 25 - 50 50 - 100 100 - 200 200 - 400 >400	Moisture Condition D Dry M Moist W Wet W _p Plastic Limit W _L Liquid Limit
	Field Tests PID Photoionisation detector reading (ppm) DCP(x-y) Dynamic penetrometer test (test depth interval shown) HP Hand Penetrometer test (UCS kPa)	Density V Very Loose L Loose MD Medium Dense D Dense VD Very Dense	Density Index <15% Density Index 15 - 35% Density Index 35 - 65% Density Index 65 - 85% Density Index 85 - 100%	



ENGINEERING LOG - BOREHOLE

CLIENT: MCCLOY PROJECT MANAGEMENT PTY LTD
PROJECT: HEREFORD HILL - STAGES 15 & 16
LOCATION: LOCHINVAR

BOREHOLE NO: BH1609
PAGE: 1 OF 1
JOB NO: NEW17P-0054F
LOGGED BY: BE
DATE: 26/4/22

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER ATTACHMENT **SURFACE RL:**
BOREHOLE DIAMETER: 300 mm **DATUM:**

Drilling and Sampling				Material description and profile information					Field Test		Structure and additional observations			
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics, colour, minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type		Result		
AD/T	Not Encountered	U50	0.60m 0.75m	0.5		CH	0.10m TOPSOIL: Sandy CLAY - medium to high plasticity, brown, fine grained sand, trace rootlets.	M > W _p	VSt	HP	190	TOPSOIL		
						CH	0.30m CLAY - medium to high plasticity, dark grey with some brown.				St	HP	140	COLLUVIUM
						CH	CLAY - medium to high plasticity, brown.				HP	200	RESIDUAL SOIL	
						CH	1.20m Clayey Gravelly SAND / Clayey Sandy GRAVEL - fine to coarse grained, pale brown, fine grained angular gravel, fines of low plasticity.				D - M	D	HP	220
				2.0		SC	2.00m Hole Terminated at 2.00 m							

LEGEND:

Water

- Water Level (Date and time shown)
- Water Inflow
- Water Outflow

Strata Changes

- Gradational or transitional strata
- Definitive or distinct strata change

Notes, Samples and Tests

- U₃₀ 50mm Diameter tube sample
- CBR Bulk sample for CBR testing
- E Environmental sample (Glass jar, sealed and chilled on site)
- ASS Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
- B Bulk Sample

Field Tests

- PID Photoionisation detector reading (ppm)
- DCP(x-y) Dynamic penetrometer test (test depth interval shown)
- HP Hand Penetrometer test (UCS kPa)

Consistency		UCS (kPa)	Moisture Condition
VS	Very Soft	<25	D Dry
S	Soft	25 - 50	M Moist
F	Firm	50 - 100	W Wet
St	Stiff	100 - 200	W _p Plastic Limit
VSt	Very Stiff	200 - 400	W _L Liquid Limit
H	Hard	>400	
Fb	Friable		
Density			
V	Very Loose		Density Index <15%
L	Loose		Density Index 15 - 35%
MD	Medium Dense		Density Index 35 - 65%
D	Dense		Density Index 65 - 85%
VD	Very Dense		Density Index 85 - 100%

OT.LIB.1.1.GLB.Log_NON-CORED BOREHOLE - TEST PIT 00-TEMPLATE LOGS SHEET.GPJ <<DrawingFile>>_06/06/2022_16:08_10.02.00.04_Datgel.Lab and in Situ Tool

ENGINEERING LOG - BOREHOLE

CLIENT: MCCLOY PROJECT MANAGEMENT PTY LTD
PROJECT: HEREFORD HILL - STAGES 15 & 16
LOCATION: LOCHINVAR

BOREHOLE NO: BH1610
PAGE: 1 OF 1
JOB NO: NEW17P-0054F
LOGGED BY: BE
DATE: 27/4/22

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER ATTACHMENT **SURFACE RL:**
BOREHOLE DIAMETER: 300 mm **DATUM:**

Drilling and Sampling				Material description and profile information					Field Test		Structure and additional observations		
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics, colour, minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type		Result	
AD/T	Not Encountered	0.50m		0.5		CH	FILL-TOPSOIL: Sandy CLAY - medium to high plasticity, grey-brown, fine to medium grained sand, trace fine grained angular gravel, root affected.	M > W _p	St	HP	180	FILL - TOPSOIL	
		U50 0.63m										FILL - CONTROLLED	
		1.00m		1.0		CH					HP	160	
		U50 1.20m									HP	200	
				1.5							HP	200	
				2.0			Hole Terminated at 2.00 m						

LEGEND:

Water

- Water Level (Date and time shown)
- Water Inflow
- Water Outflow

Strata Changes

- Gradational or transitional strata
- Definitive or distinct strata change

Notes, Samples and Tests

- U₃₀ 50mm Diameter tube sample
- CBR Bulk sample for CBR testing
- E Environmental sample (Glass jar, sealed and chilled on site)
- ASS Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
- B Bulk Sample

Field Tests

- PID Photoionisation detector reading (ppm)
- DCP(x-y) Dynamic penetrometer test (test depth interval shown)
- HP Hand Penetrometer test (UCS kPa)

Consistency		UCS (kPa)	Moisture Condition	
VS	Very Soft	<25	D	Dry
S	Soft	25 - 50	M	Moist
F	Firm	50 - 100	W	Wet
St	Stiff	100 - 200	W _p	Plastic Limit
VSt	Very Stiff	200 - 400	W _L	Liquid Limit
H	Hard	>400		
Fb	Friable			
Density		V	Very Loose	Density Index <15%
L	Loose			Density Index 15 - 35%
MD	Medium Dense			Density Index 35 - 65%
D	Dense			Density Index 65 - 85%
VD	Very Dense			Density Index 85 - 100%



ENGINEERING LOG - BOREHOLE

CLIENT: MCCLOY PROJECT MANAGEMENT PTY LTD
PROJECT: HEREFORD HILL - STAGES 15 & 16
LOCATION: LOCHINVAR

BOREHOLE NO: BH1611
PAGE: 1 OF 1
JOB NO: NEW17P-0054F
LOGGED BY: BE
DATE: 27/4/22

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER ATTACHMENT **SURFACE RL:**
BOREHOLE DIAMETER: 300 mm **DATUM:**

Drilling and Sampling				Material description and profile information					Field Test		Structure and additional observations					
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics, colour, minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type		Result				
AD/T	Not Encountered			0.50m		CH	FILL-TOPSOIL: Sandy CLAY - medium to high plasticity, grey-brown, fine to medium grained sand, trace fine grained angular gravel, root affected. / FILL: CLAY - medium to high plasticity, brown with some grey-brown trace orange, trace fine grained sand, trace fine to medium grained angular gravel.	M > Wp	St	HP	180	FILL - TOPSOIL				
				0.75m		CH				HP	160	FILL - CONTROLLED				
				1.00m						HP	180					
				1.15m						HP	180					
						1.40m	CH			FILL: CLAY - medium to high plasticity, grey-brown to brown.			HP	180		
						1.70m	CH			FILL: CLAY - medium to high plasticity, grey-brown to brown, trace grey to dark grey.			HP	160		
						2.00m	CH						VSt	HP	250	
				2.00m												
							Hole Terminated at 2.00 m									

LEGEND:
Water
 Water Level (Date and time shown)
 Water Inflow
 Water Outflow
Strata Changes
 Gradational or transitional strata
 Definitive or distinct strata change

Notes, Samples and Tests
 U₃₀ 50mm Diameter tube sample
 CBR Bulk sample for CBR testing
 E Environmental sample (Glass jar, sealed and chilled on site)
 ASS Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
 B Bulk Sample
Field Tests
 PID Photoionisation detector reading (ppm)
 DCP(x-y) Dynamic penetrometer test (test depth interval shown)
 HP Hand Penetrometer test (UCS kPa)

Consistency		UCS (kPa)	Moisture Condition
VS	Very Soft	<25	D Dry
S	Soft	25 - 50	M Moist
F	Firm	50 - 100	W Wet
St	Stiff	100 - 200	W _p Plastic Limit
VSt	Very Stiff	200 - 400	W _L Liquid Limit
H	Hard	>400	
Fb	Friable		
Density			
V	Very Loose		Density Index <15%
L	Loose		Density Index 15 - 35%
MD	Medium Dense		Density Index 35 - 65%
D	Dense		Density Index 65 - 85%
VD	Very Dense		Density Index 85 - 100%



ENGINEERING LOG - BOREHOLE

CLIENT: MCCLOY PROJECT MANAGEMENT PTY LTD

PROJECT: HEREFORD HILL - STAGES 15 & 16

LOCATION: LOCHINVAR

BOREHOLE NO: **BH1612**

PAGE: 1 OF 1

JOB NO: NEW17P-0054F

LOGGED BY: BE

DATE: 27/4/22

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER ATTACHMENT SURFACE RL:
BOREHOLE DIAMETER: 300 mm DATUM:

Drilling and Sampling				Material description and profile information				Field Test		Structure and additional observations								
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics, colour, minor components	MOISTURE CONDITION	CONSISTENCY DENSITY		Test Type	Result						
AD/T	Not Encountered					CH	FILL-TOPSOIL: Sandy CLAY - medium to high plasticity, grey-brown, fine to medium grained sand, trace fine grained angular gravel, root affected.	M > W _p				FILL - TOPSOIL						
				0.15m											FILL - CONTROLLED			
		0.40m											St	HP	180			
		U50				0.5									HP	180		
		0.55m													HP	210		
																HP	250	
		1.00m				1.0					CH					HP	220	
		U50													VSt	HP	250	
		1.15m														HP	220	
							1.5									HP	200	
				1.80m			CLAY - medium to high plasticity, grey with some brown.						COLLUVIUM / POSSIBLE FILL-CONTROLLED					
				2.0		CH				St	HP	180						
Hole Terminated at 2.00 m																		

LEGEND:

Water

- Water Level (Date and time shown)
- Water Inflow
- Water Outflow

Strata Changes

- Gradational or transitional strata
- Definitive or distinct strata change

Notes, Samples and Tests

- U₃₀ 50mm Diameter tube sample
- CBR Bulk sample for CBR testing
- E Environmental sample (Glass jar, sealed and chilled on site)
- ASS Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
- B Bulk Sample

Field Tests

- PID Photoionisation detector reading (ppm)
- DCP(x-y) Dynamic penetrometer test (test depth interval shown)
- HP Hand Penetrometer test (UCS kPa)

Consistency		UCS (kPa)	Moisture Condition
VS	Very Soft	<25	D Dry
S	Soft	25 - 50	M Moist
F	Firm	50 - 100	W Wet
St	Stiff	100 - 200	W _p Plastic Limit
VSt	Very Stiff	200 - 400	W _L Liquid Limit
H	Hard	>400	
Fb	Friable		
Density			
V	Very Loose		Density Index <15%
L	Loose		Density Index 15 - 35%
MD	Medium Dense		Density Index 35 - 65%
D	Dense		Density Index 65 - 85%
VD	Very Dense		Density Index 85 - 100%

OT.LIB.1.1.GLB.Log_NON-CORED BOREHOLE - TEST.PIT.00-TEMPLATE LOGS SHEET.GPJ <-DrawingFile> 06/06/2022 16:08 10.02.00.04 Datgel Lab and in Situ Tool



ENGINEERING LOG - BOREHOLE

CLIENT: MCCLOY PROJECT MANAGEMENT PTY LTD
PROJECT: HEREFORD HILL - STAGES 15 & 16
LOCATION: LOCHINVAR

BOREHOLE NO: BH1613
PAGE: 1 OF 1
JOB NO: NEW17P-0054F
LOGGED BY: BE
DATE: 27/4/22

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER ATTACHMENT **SURFACE RL:**
BOREHOLE DIAMETER: 300 mm **DATUM:**

Drilling and Sampling				Material description and profile information					Field Test		Structure and additional observations							
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics, colour, minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type		Result						
AD/T	Not Encountered	0.50m		0.5		CH	0.10m FILL-TOPSOIL: Sandy CLAY - medium to high plasticity, grey-brown, fine to medium grained sand, trace fine grained angular gravel, root affected. FILL: CLAY - medium to high plasticity, brown with some grey-brown trace orange, trace fine grained sand, trace fine to medium grained angular gravel.	M > W _p		HP	180	FILL - TOPSOIL						
		U50											FILL - CONTROLLED					
		0.65m																
		1.00m		1.0											St	HP	190	
		U50														HP	200	
		1.15m		1.5			1.50m			HP	180							
				2.0		GC	Extremely Weathered Andesite with soil properties; breaks down into Clayey Sandy GRAVEL - fine to medium grained angular, grey to brown with some orange, fine to coarse grained sand, fines of medium plasticity.		VSt / Fb			EXTREMELY WEATHERED ROCK						
							Hole Terminated at 2.00 m Very slow progress											

LEGEND:

Water

- Water Level (Date and time shown)
- Water Inflow
- Water Outflow

Strata Changes

- Gradational or transitional strata
- Definitive or distinct strata change

Notes, Samples and Tests

- U₃₀ 50mm Diameter tube sample
- CBR Bulk sample for CBR testing
- E Environmental sample (Glass jar, sealed and chilled on site)
- ASS Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
- B Bulk Sample

Field Tests

- PID Photoionisation detector reading (ppm)
- DCP(x-y) Dynamic penetrometer test (test depth interval shown)
- HP Hand Penetrometer test (UCS kPa)

Consistency		UCS (kPa)	Moisture Condition
VS	Very Soft	<25	D Dry
S	Soft	25 - 50	M Moist
F	Firm	50 - 100	W Wet
St	Stiff	100 - 200	W _p Plastic Limit
VSt	Very Stiff	200 - 400	W _L Liquid Limit
H	Hard	>400	
Fb	Friable		
Density			
V	Very Loose		Density Index <15%
L	Loose		Density Index 15 - 35%
MD	Medium Dense		Density Index 35 - 65%
D	Dense		Density Index 65 - 85%
VD	Very Dense		Density Index 85 - 100%

OT.LIB.1.1.GLB.Log_NON-CORED BOREHOLE - TEST PIT 00-TEMPLATE LOGS SHEET.GPJ <<DrawingFile>> 06/06/2022 16:09 10.02.00.04 Datgel Lab and in Situ Tool

ENGINEERING LOG - BOREHOLE

CLIENT: MCCLOY PROJECT MANAGEMENT PTY LTD
PROJECT: HEREFORD HILL - STAGES 15 & 16
LOCATION: LOCHINVAR

BOREHOLE NO: BH1614
PAGE: 1 OF 1
JOB NO: NEW17P-0054F
LOGGED BY: BE
DATE: 27/4/22

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER ATTACHMENT **SURFACE RL:**
BOREHOLE DIAMETER: 300 mm **DATUM:**

Drilling and Sampling				Material description and profile information					Field Test		Structure and additional observations	
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics, colour, minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type		Result
AD/T	Not Encountered	U50		0.70m	0.5	CH	FILL-TOPSOIL: Sandy CLAY - medium to high plasticity, grey-brown, fine to medium grained sand, trace fine grained angular gravel, root affected.	M < W _p				FILL - TOPSOIL
						CH	FILL: CLAY - medium to high plasticity, brown with some grey-brown trace orange, trace fine grained sand, trace fine to medium grained angular gravel.			HP	200	FILL - CONTROLLED / POSSIBLE RESIDUAL SOIL
						CH				HP	250	
						CH				HP	260	
				0.95m	1.0	CH	CLAY - medium to high plasticity, pale brown.	M > W _p	VSt	HP	250	RESIDUAL SOIL
				2.0	2.00m	CH				HP	260	
Hole Terminated at 2.00 m												

LEGEND: Water Water Level (Date and time shown) Water Inflow Water Outflow Strata Changes Gradational or transitional strata Definitive or distinct strata change	Notes, Samples and Tests U ₃₀ 50mm Diameter tube sample CBR Bulk sample for CBR testing E Environmental sample (Glass jar, sealed and chilled on site) ASS Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled) B Bulk Sample	Consistency VS Very Soft S Soft F Firm St Stiff VSt Very Stiff H Hard Fb Friable	UCS (kPa) <25 25 - 50 50 - 100 100 - 200 200 - 400 >400	Moisture Condition D Dry M Moist W Wet W _p Plastic Limit W _L Liquid Limit
	Field Tests PID Photoionisation detector reading (ppm) DCP(x-y) Dynamic penetrometer test (test depth interval shown) HP Hand Penetrometer test (UCS kPa)	Density V Very Loose L Loose MD Medium Dense D Dense VD Very Dense	Density Index <15% Density Index 15 - 35% Density Index 35 - 65% Density Index 65 - 85% Density Index 85 - 100%	



ENGINEERING LOG - BOREHOLE

CLIENT: MCCLOY PROJECT MANAGEMENT PTY LTD
 PROJECT: HEREFORD HILL - STAGES 15 & 16
 LOCATION: LOCHINVAR

BOREHOLE NO: **BH1615**
 PAGE: 1 OF 1
 JOB NO: NEW17P-0054F
 LOGGED BY: BE
 DATE: 27/4/22

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER ATTACHMENT SURFACE RL:
 BOREHOLE DIAMETER: 300 mm DATUM:

Drilling and Sampling				Material description and profile information					Field Test		Structure and additional observations			
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics, colour, minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type		Result		
AD/T	Not Encountered	U50		0.70m		CH	FILL-TOPSOIL: Sandy CLAY - medium to high plasticity, grey-brown, fine to medium grained sand, trace fine grained angular gravel, root affected.	M > w _p	St	HP	100	FILL - TOPSOIL		
				0.90m		CH	FILL: CLAY - medium to high plasticity, brown with some grey-brown trace orange, trace fine grained sand, trace fine to medium grained angular gravel.					FILL - CONTROLLED		
							CLAY - medium to high plasticity, brown.					RESIDUAL SOIL		
						CH						HP	150	
						CH						HP	180	
			1.00m	SP	Extremely Weathered Andesite with soil properties; breaks down into Gravelly SAND - fine to coarse grained, pale grey and pale brown, fine to medium grained angular gravel, with some fines of low to medium plasticity.	D - M	D	HP	140	EXTREMELY WEATHERED ROCK				
			2.00m		Hole Terminated at 2.00 m Slow progress									

LEGEND:
Water
 Water Level (Date and time shown)
 Water Inflow
 Water Outflow
Strata Changes
 --- Gradational or transitional strata
 — Definitive or distinct strata change

Notes, Samples and Tests
 U₃₀ 50mm Diameter tube sample
 CBR Bulk sample for CBR testing
 E Environmental sample (Glass jar, sealed and chilled on site)
 ASS Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
 B Bulk Sample
Field Tests
 PID Photoionisation detector reading (ppm)
 DCP(x-y) Dynamic penetrometer test (test depth interval shown)
 HP Hand Penetrometer test (UCS kPa)

Consistency		UCS (kPa)	Moisture Condition	
VS	Very Soft	<25	D	Dry
S	Soft	25 - 50	M	Moist
F	Firm	50 - 100	W	Wet
St	Stiff	100 - 200	W _p	Plastic Limit
VSt	Very Stiff	200 - 400	W _L	Liquid Limit
H	Hard	>400		
Fb	Friable			
Density		V	Very Loose	Density Index <15%
L	Loose			Density Index 15 - 35%
MD	Medium Dense			Density Index 35 - 65%
D	Dense			Density Index 65 - 85%
VD	Very Dense			Density Index 85 - 100%



ENGINEERING LOG - BOREHOLE

CLIENT: MCCLOY PROJECT MANAGEMENT PTY LTD
PROJECT: HEREFORD HILL - STAGES 15 & 16
LOCATION: LOCHINVAR

BOREHOLE NO: BH1616
PAGE: 1 OF 1
JOB NO: NEW17P-0054F
LOGGED BY: BE
DATE: 27/4/22

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER ATTACHMENT **SURFACE RL:**
BOREHOLE DIAMETER: 300 mm **DATUM:**

Drilling and Sampling				Material description and profile information					Field Test		Structure and additional observations						
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics, colour, minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type		Result					
AD/T	Not Encountered	0.50m		0.5		CH	TOPSOIL: Sandy CLAY - medium to high plasticity, brown, fine grained sand, trace rootlets.	M > W _p	St	HP	180	TOPSOIL					
		U50															
		0.70m															
		1.00m		1.0													
		U50		1.20m			CLAY - medium to high plasticity, brown.			HP	160	RESIDUAL SOIL					
				1.40m		GC	Clayey Sandy GRAVEL - fine to medium grained angular, pale grey and pale brown, fine to coarse grained sand, fines of low plasticity.	D - M	D			EXTREMELY WEATHERED ROCK					
				2.00m			Hole Terminated at 2.00 m										

LEGEND:

Water

- Water Level (Date and time shown)
- Water Inflow
- Water Outflow

Strata Changes

- Gradational or transitional strata
- Definitive or distinct strata change

Notes, Samples and Tests

- U₃₀ 50mm Diameter tube sample
- CBR Bulk sample for CBR testing
- E Environmental sample (Glass jar, sealed and chilled on site)
- ASS Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
- B Bulk Sample

Field Tests

- PID Photoionisation detector reading (ppm)
- DCP(x-y) Dynamic penetrometer test (test depth interval shown)
- HP Hand Penetrometer test (UCS kPa)

Consistency	UCS (kPa)	Moisture Condition
VS Very Soft	<25	D Dry
S Soft	25 - 50	M Moist
F Firm	50 - 100	W Wet
St Stiff	100 - 200	W _p Plastic Limit
VSt Very Stiff	200 - 400	W _L Liquid Limit
H Hard	>400	
Fb Friable		
Density	V Very Loose	Density Index <15%
L Loose	MD Medium Dense	Density Index 15 - 35%
D Dense	D Very Dense	Density Index 35 - 65%
VD Very Dense		Density Index 65 - 85%
		Density Index 85 - 100%

OT.LIB.1.1.GLB.Log.NON-CORED.BOREHOLE - TEST.PIT.00-TEMPLATE.LOGS.SHEET.GPJ <-DrawingFile> 06/06/2022.16:09.10.02.00.04.Datgel.Lab.and.in.Sku.Tool

APPENDIX B:

Results of Laboratory Testing


Report No: SSI:NEW22W-1266-S01

Issue No: 1

Shrink Swell Index Report

Client: McCloy Project Management Pty Ltd
 PO Box 2214
 Dangar NSW 2309

Project No.: NEW17P-0054F
Project Name: Hereford Hill Stage 15 & 16
Project Location: 853 New England Highway, Lochinvar



Accredited for compliance with ISO/IEC 17025-Testing. The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.
 Results provided relate only to the items tested or sampled.

B. Cullen
 Approved Signatory: Brent Cullen
 (Engineering Geologist)
 NATA Accredited Laboratory Number: 18686
 Date of Issue: 17/05/2022


Sample Details

Sample ID: NEW22W-1266-S01
Sampling Method: The results outlined below apply to the sample as received
Material: Clay
Source: On-Site Insitu
Specification: No Specification
Sample Location: BH1501 - (0.50 - 0.65m)
Date Tested: 5/05/2022

Date Sampled: 26/04/2022
Date Submitted: 4/05/2022

Swell Test AS 1289.7.1.1		Shrink Test AS 1289.7.1.1	
Swell on Saturation (%):	3.8	Shrink on drying (%):	6.3
Moisture Content before (%):	30.9	Shrinkage Moisture Content (%):	29.7
Moisture Content after (%):	39.6	Est. inert material (%):	1%
Est. Unc. Comp. Strength before (kPa):	310	Crumbling during shrinkage:	Nil
Est. Unc. Comp. Strength after (kPa):	150	Cracking during shrinkage:	Nil

Shrink Swell



Shrink Swell Index - Iss (%): 4.6

Comments


Report No: SSI:NEW22W-1266-S02

Issue No: 1

Shrink Swell Index Report

Client: McCloy Project Management Pty Ltd
 PO Box 2214
 Dangar NSW 2309

Project No.: NEW17P-0054F
Project Name: Hereford Hill Stage 15 & 16
Project Location: 853 New England Highway, Lochinvar



Accredited for compliance with ISO/IEC 17025-Testing. The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.
 Results provided relate only to the items tested or sampled.


B. Cullen
 Approved Signatory: Brent Cullen
 (Engineering Geologist)
 NATA Accredited Laboratory Number: 18686
 Date of Issue: 17/05/2022

Sample Details

Sample ID: NEW22W-1266-S02
Sampling Method: The results outlined below apply to the sample as received
Material: Clay
Date Sampled: 26/04/2022
Source: On-Site Insitu
Date Submitted: 4/05/2022
Specification: No Specification
Sample Location: BH1502 - (0.50 - 0.64m)
Date Tested: 5/05/2022

Swell Test AS 1289.7.1.1		Shrink Test AS 1289.7.1.1	
Swell on Saturation (%):	-0.8	Shrink on drying (%):	1.9
Moisture Content before (%):	19.8	Shrinkage Moisture Content (%):	20.4
Moisture Content after (%):	23.6	Est. inert material (%):	4%
Est. Unc. Comp. Strength before (kPa):	470	Crumbling during shrinkage:	Nil
Est. Unc. Comp. Strength after (kPa):	340	Cracking during shrinkage:	Major

Shrink Swell



Shrink Swell Index - Iss (%): 1.1

Comments


Report No: SSI:NEW22W-1266-S03

Issue No: 1

Shrink Swell Index Report

Client: McCloy Project Management Pty Ltd
 PO Box 2214
 Dangar NSW 2309

Project No.: NEW17P-0054F
Project Name: Hereford Hill Stage 15 & 16
Project Location: 853 New England Highway, Lochinvar



Accredited for compliance with ISO/IEC 17025-Testing. The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.
 Results provided relate only to the items tested or sampled.

B. Cullen
 Approved Signatory: Brent Cullen
 (Engineering Geologist)
 NATA Accredited Laboratory Number: 18686
 Date of Issue: 17/05/2022

Sample Details


Sample ID: NEW22W-1266-S03
Sampling Method: The results outlined below apply to the sample as received
Material: Clay
Source: On-Site Insitu
Specification: No Specification
Sample Location: BH1503 - (0.60 - 0.85m)
Date Tested: 5/05/2022

Date Sampled: 26/04/2022
Date Submitted: 4/05/2022

Swell Test		AS 1289.7.1.1
Swell on Saturation (%):	-0.4	
Moisture Content before (%):	42.9	
Moisture Content after (%):	44.2	
Est. Unc. Comp. Strength before (kPa):	90	
Est. Unc. Comp. Strength after (kPa):	70	

Shrink Test		AS 1289.7.1.1
Shrink on drying (%):	10.2	
Shrinkage Moisture Content (%):	42.3	
Est. inert material (%):	1%	
Crumbling during shrinkage:	Nil	
Cracking during shrinkage:	Nil	

Shrink Swell





Shrink Swell Index - Iss (%): 5.7

Comments

Shrink Swell Index Report

Client: McCloy Project Management Pty Ltd
 PO Box 2214
 Dangar NSW 2309

Project No.: NEW17P-0054F
Project Name: Hereford Hill Stage 15 & 16
Project Location: 853 New England Highway, Lochinvar


 Accredited for compliance with ISO/IEC 17025-Testing.
 The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.
 Results provided relate only to the items tested or sampled.

 Approved Signatory: Brent Cullen
 (Engineering Geologist)
 NATA Accredited Laboratory Number: 18686
 Date of Issue: 17/05/2022


Sample Details

Sample ID: NEW22W-1266-S04
Sampling Method: The results outlined below apply to the sample as received
Material: Clay
Source: On-Site Insitu
Specification: No Specification
Sample Location: BH1504 - (0.50 - 0.64m)
Date Tested: 5/05/2022

Date Sampled: 26/04/2022
Date Submitted: 4/05/2022

Swell Test AS 1289.7.1.1		Shrink Test AS 1289.7.1.1	
Swell on Saturation (%):	2.1	Shrink on drying (%):	7.3
Moisture Content before (%):	32.0	Shrinkage Moisture Content (%):	31.7
Moisture Content after (%):	37.8	Est. inert material (%):	1%
Est. Unc. Comp. Strength before (kPa):	290	Crumbling during shrinkage:	Nil
Est. Unc. Comp. Strength after (kPa):	150	Cracking during shrinkage:	Minor

Shrink Swell



Shrink Swell Index - Iss (%): 4.6

Comments

(This area is reserved for comments and observations.)


Report No: SSI:NEW22W-1266-S05

Issue No: 1

Shrink Swell Index Report

Client: McCloy Project Management Pty Ltd
 PO Box 2214
 Dangar NSW 2309

Project No.: NEW17P-0054F
Project Name: Hereford Hill Stage 15 & 16
Project Location: 853 New England Highway, Lochinvar



Accredited for compliance with ISO/IEC 17025-Testing. The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.
 Results provided relate only to the items tested or sampled.

B. Cullen
 Approved Signatory: Brent Cullen
 (Engineering Geologist)
 NATA Accredited Laboratory Number: 18686
 Date of Issue: 17/05/2022


Sample Details

Sample ID: NEW22W-1266-S05
Sampling Method: The results outlined below apply to the sample as received
Material: Clay
Source: On-Site Insitu
Specification: No Specification
Sample Location: BH1505 - (0.20 - 0.35m)
Date Tested: 5/05/2022

Date Sampled: 26/04/2022
Date Submitted: 4/05/2022

Swell Test AS 1289.7.1.1		Shrink Test AS 1289.7.1.1	
Swell on Saturation (%):	0.1	Shrink on drying (%):	2.5
Moisture Content before (%):	25.3	Shrinkage Moisture Content (%):	22.9
Moisture Content after (%):	32.0	Est. inert material (%):	5%
Est. Unc. Comp. Strength before (kPa):	280	Crumbling during shrinkage:	Nil
Est. Unc. Comp. Strength after (kPa):	360	Cracking during shrinkage:	Major

Shrink Swell



Shrink Swell Index - Iss (%): 1.4

Comments


Report No: SSI:NEW22W-1266-S06

Issue No: 1

Shrink Swell Index Report

Client: McCloy Project Management Pty Ltd
 PO Box 2214
 Dangar NSW 2309

Project No.: NEW17P-0054F
Project Name: Hereford Hill Stage 15 & 16
Project Location: 853 New England Highway, Lochinvar



Accredited for compliance with ISO/IEC 17025-Testing. The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.
 Results provided relate only to the items tested or sampled.


B. Cullen
 Approved Signatory: Brent Cullen
 (Engineering Geologist)
 NATA Accredited Laboratory Number: 18686
 Date of Issue: 17/05/2022

Sample Details

Sample ID: NEW22W-1266-S06
Sampling Method: The results outlined below apply to the sample as received
Material: Clay
Date Sampled: 26/04/2022
Source: On-Site Insitu
Date Submitted: 4/05/2022
Specification: No Specification
Sample Location: BH1506 - (0.35 - 0.60m)
Date Tested: 5/05/2022

Swell Test AS 1289.7.1.1		Shrink Test AS 1289.7.1.1	
Swell on Saturation (%):	1.2	Shrink on drying (%):	7.3
Moisture Content before (%):	26.4	Shrinkage Moisture Content (%):	26.7
Moisture Content after (%):	28.1	Est. inert material (%):	1%
Est. Unc. Comp. Strength before (kPa):	480	Crumbling during shrinkage:	Nil
Est. Unc. Comp. Strength after (kPa):	280	Cracking during shrinkage:	Nil

Shrink Swell



Shrink Swell Index - Iss (%): 4.4

Comments


Report No: SSI:NEW22W-1266-S07

Issue No: 1

Shrink Swell Index Report

Client: McCloy Project Management Pty Ltd
 PO Box 2214
 Dangar NSW 2309

Project No.: NEW17P-0054F
Project Name: Hereford Hill Stage 15 & 16
Project Location: 853 New England Highway, Lochinvar



Accredited for compliance with ISO/IEC 17025-Testing. The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.
 Results provided relate only to the items tested or sampled.


B. Cullen
 Approved Signatory: Brent Cullen
 (Engineering Geologist)
 NATA Accredited Laboratory Number: 18686
 Date of Issue: 17/05/2022

Sample Details

Sample ID: NEW22W-1266-S07
Sampling Method: The results outlined below apply to the sample as received
Material: Clay
Date Sampled: 26/04/2022
Source: On-Site Insitu
Date Submitted: 4/05/2022
Specification: No Specification
Sample Location: BH1507 - (0.50 - 0.65m)
Date Tested: 5/05/2022

Swell Test AS 1289.7.1.1		Shrink Test AS 1289.7.1.1	
Swell on Saturation (%):	-0.1	Shrink on drying (%):	8.4
Moisture Content before (%):	35.8	Shrinkage Moisture Content (%):	33.4
Moisture Content after (%):	37.5	Est. inert material (%):	1%
Est. Unc. Comp. Strength before (kPa):	150	Crumbling during shrinkage:	Nil
Est. Unc. Comp. Strength after (kPa):	150	Cracking during shrinkage:	Nil

Shrink Swell



Shrink Swell Index - Iss (%): 4.7

Comments


Report No: SSI:NEW22W-1266-S08

Issue No: 1

Shrink Swell Index Report

Client: McCloy Project Management Pty Ltd
 PO Box 2214
 Dangar NSW 2309

Project No.: NEW17P-0054F
Project Name: Hereford Hill Stage 15 & 16
Project Location: 853 New England Highway, Lochinvar



Accredited for compliance with ISO/IEC 17025-Testing.
 The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.
 Results provided relate only to the items tested or sampled.

B. Cullen
 Approved Signatory: Brent Cullen
 (Engineering Geologist)
 NATA Accredited Laboratory Number: 18686
 Date of Issue: 17/05/2022


Sample Details

Sample ID: NEW22W-1266-S08
Sampling Method: The results outlined below apply to the sample as received
Material: Clay
Source: On-Site Insitu
Specification: No Specification
Sample Location: BH1508 - (0.20 - 0.33m)
Date Tested: 5/05/2022

Date Sampled: 26/04/2022
Date Submitted: 4/05/2022

Swell Test AS 1289.7.1.1		Shrink Test AS 1289.7.1.1	
Swell on Saturation (%):	0.6	Shrink on drying (%):	5.7
Moisture Content before (%):	25.0	Shrinkage Moisture Content (%):	24.3
Moisture Content after (%):	28.5	Est. inert material (%):	1%
Est. Unc. Comp. Strength before (kPa):	480	Crumbling during shrinkage:	Nil
Est. Unc. Comp. Strength after (kPa):	370	Cracking during shrinkage:	Nil

Shrink Swell



Shrink Swell Index - Iss (%): 3.4

Comments


Report No: SSI:NEW22W-1266-S09

Issue No: 1

Shrink Swell Index Report

Client: McCloy Project Management Pty Ltd
 PO Box 2214
 Dangar NSW 2309

Project No.: NEW17P-0054F
Project Name: Hereford Hill Stage 15 & 16
Project Location: 853 New England Highway, Lochinvar



Accredited for compliance with ISO/IEC 17025-Testing. The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.
 Results provided relate only to the items tested or sampled.

B. Cullen
 Approved Signatory: Brent Cullen
 (Engineering Geologist)
 NATA Accredited Laboratory Number: 18686
 Date of Issue: 17/05/2022

Sample Details


Sample ID: NEW22W-1266-S09
Sampling Method: The results outlined below apply to the sample as received
Material: Clay
Source: On-Site Insitu
Specification: No Specification
Sample Location: BH1601 - (0.50 - 0.70m)
Date Tested: 5/05/2022

Date Sampled: 26/04/2022
Date Submitted: 4/05/2022

Swell Test		AS 1289.7.1.1
Swell on Saturation (%):	-0.7	
Moisture Content before (%):	32.9	
Moisture Content after (%):	34.9	
Est. Unc. Comp. Strength before (kPa):	250	
Est. Unc. Comp. Strength after (kPa):	210	

Shrink Test		AS 1289.7.1.1
Shrink on drying (%):	8.4	
Shrinkage Moisture Content (%):	32.5	
Est. inert material (%):	1%	
Crumbling during shrinkage:	Nil	
Cracking during shrinkage:	Nil	

Shrink Swell



Shrink Swell Index - Iss (%): 4.7

Comments


Shrink Swell Index Report

Client: McCloy Project Management Pty Ltd
 PO Box 2214
 Dangar NSW 2309

Project No.: NEW17P-0054F

Project Name: Hereford Hill Stage 15 & 16

Project Location: 853 New England Highway, Lochinvar



Accredited for compliance with ISO/IEC 17025-Testing. The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.

Results provided relate only to the items tested or sampled.

B. Cullen
 Approved Signatory: Brent Cullen
 (Engineering Geologist)
 NATA Accredited Laboratory Number: 18686
 Date of Issue: 17/05/2022

Sample Details

Sample ID: NEW22W-1266-S10

Sampling Method: The results outlined below apply to the sample as received

Material: Clay

Source: On-Site Insitu

Specification: No Specification

Sample Location: BH1602 - (0.50 - 0.70m)

Date Tested: 5/05/2022


Date Sampled: 26/04/2022

Date Submitted: 4/05/2022

Swell Test		AS 1289.7.1.1
Swell on Saturation (%):	0.4	
Moisture Content before (%):	29.4	
Moisture Content after (%):	28.3	
Est. Unc. Comp. Strength before (kPa):	480	
Est. Unc. Comp. Strength after (kPa):	220	

Shrink Test		AS 1289.7.1.1
Shrink on drying (%):	7.9	
Shrinkage Moisture Content (%):	26.6	
Est. inert material (%):	1%	
Crumbling during shrinkage:	Nil	
Cracking during shrinkage:	Nil	

Shrink Swell



Shrink Swell Index - Iss (%): 4.5

Comments


Report No: SSI:NEW22W-1266-S11

Issue No: 1

Shrink Swell Index Report

Client: McCloy Project Management Pty Ltd
 PO Box 2214
 Dangar NSW 2309

Project No.: NEW17P-0054F
Project Name: Hereford Hill Stage 15 & 16
Project Location: 853 New England Highway, Lochinvar



Accredited for compliance with ISO/IEC 17025-Testing. The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.
 Results provided relate only to the items tested or sampled.

B. Cullen
 Approved Signatory: Brent Cullen
 (Engineering Geologist)
 NATA Accredited Laboratory Number: 18686
 Date of Issue: 17/05/2022

Sample Details


Sample ID: NEW22W-1266-S11
Sampling Method: The results outlined below apply to the sample as received
Material: Gravelly Sandy Clay
Source: On-Site Insitu
Specification: No Specification
Sample Location: BH1602 - (1.00 - 1.15m)
Date Tested: 5/05/2022

Date Sampled: 26/04/2022
Date Submitted: 4/05/2022

Swell Test	AS 1289.7.1.1
Swell on Saturation (%):	1.0
Moisture Content before (%):	32.9
Moisture Content after (%):	35.3
Est. Unc. Comp. Strength before (kPa):	310
Est. Unc. Comp. Strength after (kPa):	210

Shrink Test	AS 1289.7.1.1
Shrink on drying (%):	4.5
Shrinkage Moisture Content (%):	34.0
Est. inert material (%):	1%
Crumbling during shrinkage:	Nil
Cracking during shrinkage:	Minor

Shrink Swell



Shrink Swell Index - Iss (%): 2.8

Comments


Report No: SSI:NEW22W-1266-S12

Issue No: 1

Shrink Swell Index Report

Client: McCloy Project Management Pty Ltd
 PO Box 2214
 Dangar NSW 2309

Project No.: NEW17P-0054F
Project Name: Hereford Hill Stage 15 & 16
Project Location: 853 New England Highway, Lochinvar



Accredited for compliance with ISO/IEC 17025-Testing.
 The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.
 Results provided relate only to the items tested or sampled.

B. Cullen
 Approved Signatory: Brent Cullen
 (Engineering Geologist)
 NATA Accredited Laboratory Number: 18686
 Date of Issue: 17/05/2022


Sample Details

Sample ID: NEW22W-1266-S12
Sampling Method: The results outlined below apply to the sample as received
Material: Clay
Source: On-Site Insitu
Specification: No Specification
Sample Location: BH1603 - (0.40 - 0.52m)
Date Tested: 5/05/2022

Date Sampled: 26/04/2022
Date Submitted: 4/05/2022

Swell Test AS 1289.7.1.1		Shrink Test AS 1289.7.1.1	
Swell on Saturation (%):	2.4	Shrink on drying (%):	3.7
Moisture Content before (%):	23.7	Shrinkage Moisture Content (%):	23.1
Moisture Content after (%):	27.6	Est. inert material (%):	3%
Est. Unc. Comp. Strength before (kPa):	500	Crumbling during shrinkage:	Nil
Est. Unc. Comp. Strength after (kPa):	220	Cracking during shrinkage:	Minor

Shrink Swell



Shrink Swell Index - Iss (%): 2.7

Comments


Report No: SSI:NEW22W-1266-S13

Issue No: 1

Shrink Swell Index Report

Client: McCloy Project Management Pty Ltd
 PO Box 2214
 Dangar NSW 2309

Project No.: NEW17P-0054F
Project Name: Hereford Hill Stage 15 & 16
Project Location: 853 New England Highway, Lochinvar



Accredited for compliance with ISO/IEC 17025-Testing. The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.
 Results provided relate only to the items tested or sampled.

B. Cullen
 Approved Signatory: Brent Cullen
 (Engineering Geologist)
 NATA Accredited Laboratory Number: 18686
 Date of Issue: 17/05/2022


Sample Details

Sample ID: NEW22W-1266-S13
Sampling Method: The results outlined below apply to the sample as received
Material: Clay
Source: On-Site Insitu
Specification: No Specification
Sample Location: BH1603 - (1.00 - 1.20m)
Date Tested: 5/05/2022

Date Sampled: 26/04/2022
Date Submitted: 4/05/2022

Swell Test AS 1289.7.1.1		Shrink Test AS 1289.7.1.1	
Swell on Saturation (%):	1.1	Shrink on drying (%):	6.6
Moisture Content before (%):	27.7	Shrinkage Moisture Content (%):	27.8
Moisture Content after (%):	34.3	Est. inert material (%):	1%
Est. Unc. Comp. Strength before (kPa):	380	Crumbling during shrinkage:	Nil
Est. Unc. Comp. Strength after (kPa):	190	Cracking during shrinkage:	Minor

Shrink Swell



Shrink Swell Index - Iss (%): 4.0

Comments


Report No: SSI:NEW22W-1266-S14

Issue No: 1

Shrink Swell Index Report

Client: McCloy Project Management Pty Ltd
 PO Box 2214
 Dangar NSW 2309

Project No.: NEW17P-0054F
Project Name: Hereford Hill Stage 15 & 16
Project Location: 853 New England Highway, Lochinvar



Accredited for compliance with ISO/IEC 17025-Testing. The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.
 Results provided relate only to the items tested or sampled.


B. Cullen
 Approved Signatory: Brent Cullen
 (Engineering Geologist)
 NATA Accredited Laboratory Number: 18686
 Date of Issue: 23/05/2022

Sample Details

Sample ID: NEW22W-1266-S14
Sampling Method: The results outlined below apply to the sample as received
Material: Clay
Date Sampled: 26/04/2022
Source: On-Site Insitu
Date Submitted: 4/05/2022
Specification: No Specification
Sample Location: BH1604 - (0.40 - 0.60m)
Date Tested: 9/05/2022

Swell Test AS 1289.7.1.1		Shrink Test AS 1289.7.1.1	
Swell on Saturation (%):	-0.6	Shrink on drying (%):	4.7
Moisture Content before (%):	27.2	Shrinkage Moisture Content (%):	26.7
Moisture Content after (%):	20.4	Est. inert material (%):	3%
Est. Unc. Comp. Strength before (kPa):	430	Crumbling during shrinkage:	Nil
Est. Unc. Comp. Strength after (kPa):	160	Cracking during shrinkage:	Major

Shrink Swell



Shrink Swell Index - Iss (%): 2.6

Comments

Shrink Swell Index Report

Client: McCloy Project Management Pty Ltd
 PO Box 2214
 Dangar NSW 2309

Project No.: NEW17P-0054F
Project Name: Hereford Hill Stage 15 & 16
Project Location: 853 New England Highway, Lochinvar



Accredited for compliance with ISO/IEC 17025-Testing. The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.

Results provided relate only to the items tested or sampled.

B. Cullen


Approved Signatory: Brent Cullen
 (Engineering Geologist)
 NATA Accredited Laboratory Number: 18686
 Date of Issue: 23/05/2022

Sample Details

Sample ID: NEW22W-1266-S15
Sampling Method: The results outlined below apply to the sample as received
Material: Clay
Source: On-Site Insitu
Specification: No Specification
Sample Location: BH1604 - (1.00 - 1.15m)
Date Tested: 9/05/2022
Date Sampled: 26/04/2022
Date Submitted: 4/05/2022

Swell Test AS 1289.7.1.1		Shrink Test AS 1289.7.1.1	
Swell on Saturation (%):	0.9	Shrink on drying (%):	4.9
Moisture Content before (%):	26.7	Shrinkage Moisture Content (%):	23.7
Moisture Content after (%):	29.8	Est. inert material (%):	2%
Est. Unc. Comp. Strength before (kPa):	420	Crumbling during shrinkage:	Nil
Est. Unc. Comp. Strength after (kPa):	220	Cracking during shrinkage:	Minor

Shrink Swell



Shrink Swell Index - Iss (%): 3.0

Comments


Shrink Swell Index Report

Client: McCloy Project Management Pty Ltd
 PO Box 2214
 Dangar NSW 2309

Project No.: NEW17P-0054F

Project Name: Hereford Hill Stage 15 & 16

Project Location: 853 New England Highway, Lochinvar



Accredited for compliance with ISO/IEC 17025-Testing. The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.

Results provided relate only to the items tested or sampled.

B. Cullen
 Approved Signatory: Brent Cullen
 (Engineering Geologist)
 NATA Accredited Laboratory Number: 18686
 Date of Issue: 23/05/2022

Sample Details

Sample ID: NEW22W-1266-S16

Sampling Method: The results outlined below apply to the sample as received

Material: Clay

Source: On-Site Insitu

Specification: No Specification

Sample Location: BH1605 - (0.40 - 0.57m)


Date Tested: 9/05/2022

Date Sampled: 26/04/2022

Date Submitted: 4/05/2022

Swell Test AS 1289.7.1.1		Shrink Test AS 1289.7.1.1	
Swell on Saturation (%):	0.7	Shrink on drying (%):	5.0
Moisture Content before (%):	25.6	Shrinkage Moisture Content (%):	24.9
Moisture Content after (%):	30.5	Est. inert material (%):	2%
Est. Unc. Comp. Strength before (kPa):	350	Crumbling during shrinkage:	Nil
Est. Unc. Comp. Strength after (kPa):	190	Cracking during shrinkage:	Major

Shrink Swell



Shrink Swell Index - Iss (%): 3.0

Comments

Report No: SSI:NEW22W-1266-S17


Issue No: 1

Shrink Swell Index Report

Client: McCloy Project Management Pty Ltd
 PO Box 2214
 Dangar NSW 2309

Project No.: NEW17P-0054F
Project Name: Hereford Hill Stage 15 & 16
Project Location: 853 New England Highway, Lochinvar

Accredited for compliance with ISO/IEC 17025-Testing. The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards. Results provided relate only to the items tested or sampled.



B. Cullen
 Approved Signatory: Brent Cullen
 (Engineering Geologist)
 NATA Accredited Laboratory Number: 18686
 Date of Issue: 23/05/2022

Sample Details


Sample ID: NEW22W-1266-S17
Sampling Method: The results outlined below apply to the sample as received
Material: Clay
Source: On-Site Insitu
Specification: No Specification
Sample Location: BH1605 - (1.00 - 1.18m)
Date Tested: 9/05/2022

Date Sampled: 26/04/2022
Date Submitted: 4/05/2022

Swell Test AS 1289.7.1.1	
Swell on Saturation (%):	1.8
Moisture Content before (%):	25.3
Moisture Content after (%):	29.9
Est. Unc. Comp. Strength before (kPa):	480
Est. Unc. Comp. Strength after (kPa):	180

Shrink Test AS 1289.7.1.1	
Shrink on drying (%):	6.0
Shrinkage Moisture Content (%):	25.0
Est. inert material (%):	2%
Crumbling during shrinkage:	Nil
Cracking during shrinkage:	Minor

Shrink Swell



Shrink Swell Index - Iss (%): 3.8

Comments


Report No: SSI:NEW22W-1266-S18

Issue No: 1

Shrink Swell Index Report

Client: McCloy Project Management Pty Ltd
 PO Box 2214
 Dangar NSW 2309

Project No.: NEW17P-0054F
Project Name: Hereford Hill Stage 15 & 16
Project Location: 853 New England Highway, Lochinvar



Accredited for compliance with ISO/IEC 17025-Testing. The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.
 Results provided relate only to the items tested or sampled.

B. Cullen
 Approved Signatory: Brent Cullen
 (Engineering Geologist)
 NATA Accredited Laboratory Number: 18686
 Date of Issue: 23/05/2022

Sample Details


Sample ID: NEW22W-1266-S18
Sampling Method: The results outlined below apply to the sample as received
Material: Clay
Source: On-Site Insitu
Specification: No Specification
Sample Location: BH1606 - (0.50 - 0.63m)
Date Tested: 9/05/2022

Date Sampled: 26/04/2022
Date Submitted: 4/05/2022

Swell Test AS 1289.7.1.1	
Swell on Saturation (%):	2.0
Moisture Content before (%):	25.5
Moisture Content after (%):	30.6
Est. Unc. Comp. Strength before (kPa):	500
Est. Unc. Comp. Strength after (kPa):	230

Shrink Test AS 1289.7.1.1	
Shrink on drying (%):	5.8
Shrinkage Moisture Content (%):	23.8
Est. inert material (%):	2%
Crumbling during shrinkage:	Nil
Cracking during shrinkage:	Nil

Shrink Swell



Shrink Swell Index - Iss (%): 3.8

Comments

Report No: SSI:NEW22W-1266-S19


Issue No: 1

Shrink Swell Index Report

Client: McCloy Project Management Pty Ltd
 PO Box 2214
 Dangar NSW 2309

Project No.: NEW17P-0054F
Project Name: Hereford Hill Stage 15 & 16
Project Location: 853 New England Highway, Lochinvar

Accredited for compliance with ISO/IEC 17025-Testing. The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards. Results provided relate only to the items tested or sampled.




B. Cullen
 Approved Signatory: Brent Cullen
 (Engineering Geologist)
 NATA Accredited Laboratory Number: 18686
 Date of Issue: 23/05/2022

Sample Details

Sample ID: NEW22W-1266-S19
Sampling Method: The results outlined below apply to the sample as received
Material: Clay
Date Sampled: 26/04/2022
Source: On-Site Insitu
Date Submitted: 4/05/2022
Specification: No Specification
Sample Location: BH1607 - (0.50 - 0.66m)
Date Tested: 9/05/2022

Swell Test AS 1289.7.1.1		Shrink Test AS 1289.7.1.1	
Swell on Saturation (%):	3.7	Shrink on drying (%):	5.0
Moisture Content before (%):	24.6	Shrinkage Moisture Content (%):	23.1
Moisture Content after (%):	30.3	Est. inert material (%):	2%
Est. Unc. Comp. Strength before (kPa):	>600	Crumbling during shrinkage:	Nil
Est. Unc. Comp. Strength after (kPa):	240	Cracking during shrinkage:	Nil

Shrink Swell



Shrink Swell Index - Iss (%): 3.8

Comments


Report No: SSI:NEW22W-1266-S20

Issue No: 1

Shrink Swell Index Report

Client: McCloy Project Management Pty Ltd
 PO Box 2214
 Dangar NSW 2309

Project No.: NEW17P-0054F
Project Name: Hereford Hill Stage 15 & 16
Project Location: 853 New England Highway, Lochinvar



Accredited for compliance with ISO/IEC 17025-Testing. The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.
 Results provided relate only to the items tested or sampled.

B. Cullen
 Approved Signatory: Brent Cullen
 (Engineering Geologist)
 NATA Accredited Laboratory Number: 18686
 Date of Issue: 23/05/2022


Sample Details

Sample ID: NEW22W-1266-S20
Sampling Method: The results outlined below apply to the sample as received
Material: Clay
Source: On-Site Insitu
Specification: No Specification
Sample Location: BH1608 - (0.40 - 0.60m)
Date Tested: 9/05/2022

Date Sampled: 26/04/2022
Date Submitted: 4/05/2022

Swell Test AS 1289.7.1.1		Shrink Test AS 1289.7.1.1	
Swell on Saturation (%):	2.6	Shrink on drying (%):	6.2
Moisture Content before (%):	27.7	Shrinkage Moisture Content (%):	25.5
Moisture Content after (%):	32.7	Est. inert material (%):	2%
Est. Unc. Comp. Strength before (kPa):	550	Crumbling during shrinkage:	Nil
Est. Unc. Comp. Strength after (kPa):	270	Cracking during shrinkage:	Minor

Shrink Swell



Shrink Swell Index - Iss (%): 4.1

Comments


Report No: SSI:NEW22W-1266-S21

Issue No: 1

Shrink Swell Index Report

Client: McCloy Project Management Pty Ltd
 PO Box 2214
 Dangar NSW 2309

Project No.: NEW17P-0054F
Project Name: Hereford Hill Stage 15 & 16
Project Location: 853 New England Highway, Lochinvar



Accredited for compliance with ISO/IEC 17025-Testing. The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.
 Results provided relate only to the items tested or sampled.

B. Cullen
 Approved Signatory: Brent Cullen
 (Engineering Geologist)
 NATA Accredited Laboratory Number: 18686
 Date of Issue: 23/05/2022


Sample Details

Sample ID: NEW22W-1266-S21
Sampling Method: The results outlined below apply to the sample as received
Material: Clay
Source: On-Site Insitu
Specification: No Specification
Sample Location: BH1609 - (0.60 - 0.75m)
Date Tested: 9/05/2022

Date Sampled: 26/04/2022
Date Submitted: 4/05/2022

Swell Test AS 1289.7.1.1		Shrink Test AS 1289.7.1.1	
Swell on Saturation (%):	0.0	Shrink on drying (%):	6.6
Moisture Content before (%):	24.5	Shrinkage Moisture Content (%):	27.8
Moisture Content after (%):	24.0	Est. inert material (%):	2%
Est. Unc. Comp. Strength before (kPa):	380	Crumbling during shrinkage:	Nil
Est. Unc. Comp. Strength after (kPa):	575	Cracking during shrinkage:	Minor

Shrink Swell



Shrink Swell Index - Iss (%): 3.7

Comments

Report No: SSI:NEW22W-1266-S22

Issue No: 1

Shrink Swell Index Report

Client: McCloy Project Management Pty Ltd
 PO Box 2214
 Dangar NSW 2309

Project No.: NEW17P-0054F
Project Name: Hereford Hill Stage 15 & 16
Project Location: 853 New England Highway, Lochinvar



Accredited for compliance with ISO/IEC 17025-Testing. The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.

Results provided relate only to the items tested or sampled.

B. Cullen

Approved Signatory: Brent Cullen
 (Engineering Geologist)
 NATA Accredited Laboratory Number: 18686
 Date of Issue: 31/05/2022


Sample Details

Sample ID: NEW22W-1266-S22
Sampling Method: The results outlined below apply to the sample as received
Material: Clay
Source: On-Site Insitu
Specification: No Specification
Sample Location: BH1610 - (0.50 - 0.63m)
Date Tested: 9/05/2022
Date Sampled: 26/04/2022
Date Submitted: 4/05/2022

Swell Test		AS 1289.7.1.1
Swell on Saturation (%):	4.0	
Moisture Content before (%):	25.6	
Moisture Content after (%):	33.6	
Est. Unc. Comp. Strength before (kPa):	380	
Est. Unc. Comp. Strength after (kPa):	160	

Shrink Test		AS 1289.7.1.1
Shrink on drying (%):	6.2	
Shrinkage Moisture Content (%):	23.9	
Est. inert material (%):	1%	
Crumbling during shrinkage:	Nil	
Cracking during shrinkage:	Moderate	

Shrink Swell



Shrink Swell Index - Iss (%): 4.5

Comments


Report No: SSI:NEW22W-1266-S23

Issue No: 1

Shrink Swell Index Report

Client: McCloy Project Management Pty Ltd
 PO Box 2214
 Dangar NSW 2309

Project No.: NEW17P-0054F
Project Name: Hereford Hill Stage 15 & 16
Project Location: 853 New England Highway, Lochinvar



Accredited for compliance with ISO/IEC 17025-Testing. The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.
 Results provided relate only to the items tested or sampled.


B. Cullen
 Approved Signatory: Brent Cullen
 (Engineering Geologist)
 NATA Accredited Laboratory Number: 18686
 Date of Issue: 23/05/2022

Sample Details

Sample ID: NEW22W-1266-S23
Sampling Method: The results outlined below apply to the sample as received
Material: Clay
Date Sampled: 26/04/2022
Source: On-Site Insitu
Date Submitted: 4/05/2022
Specification: No Specification
Sample Location: BH1610 - (1.00 - 1.20m)
Date Tested: 11/05/2022

Swell Test AS 1289.7.1.1		Shrink Test AS 1289.7.1.1	
Swell on Saturation (%):	0.0	Shrink on drying (%):	4.1
Moisture Content before (%):	29.6	Shrinkage Moisture Content (%):	29.3
Moisture Content after (%):	32.5	Est. inert material (%):	1%
Est. Unc. Comp. Strength before (kPa):	530	Crumbling during shrinkage:	Nil
Est. Unc. Comp. Strength after (kPa):	290	Cracking during shrinkage:	Minor

Shrink Swell



Shrink Swell Index - Iss (%): 2.3

Comments


Report No: SSI:NEW22W-1266-S24

Issue No: 1

Shrink Swell Index Report

Client: McCloy Project Management Pty Ltd
 PO Box 2214
 Dangar NSW 2309

Project No.: NEW17P-0054F
Project Name: Hereford Hill Stage 15 & 16
Project Location: 853 New England Highway, Lochinvar



Accredited for compliance with ISO/IEC 17025-Testing. The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.
 Results provided relate only to the items tested or sampled.


B. Cullen
 Approved Signatory: Brent Cullen
 (Engineering Geologist)
 NATA Accredited Laboratory Number: 18686
 Date of Issue: 31/05/2022

Sample Details

Sample ID: NEW22W-1266-S24
Sampling Method: The results outlined below apply to the sample as received
Material: Clay
Date Sampled: 26/04/2022
Source: On-Site Insitu
Date Submitted: 4/05/2022
Specification: No Specification
Sample Location: BH1611 - (0.50 - 0.75m)
Date Tested: 11/05/2022

Swell Test AS 1289.7.1.1		Shrink Test AS 1289.7.1.1	
Swell on Saturation (%):	2.6	Shrink on drying (%):	6.0
Moisture Content before (%):	28.2	Shrinkage Moisture Content (%):	25.8
Moisture Content after (%):	36.4	Est. inert material (%):	2%
Est. Unc. Comp. Strength before (kPa):	240	Crumbling during shrinkage:	Nil
Est. Unc. Comp. Strength after (kPa):	80	Cracking during shrinkage:	Minor

Shrink Swell



Shrink Swell Index - Iss (%): 4.0

Comments


Report No: SSI:NEW22W-1266-S25

Issue No: 1

Shrink Swell Index Report

Client: McCloy Project Management Pty Ltd
 PO Box 2214
 Dangar NSW 2309

Project No.: NEW17P-0054F
Project Name: Hereford Hill Stage 15 & 16
Project Location: 853 New England Highway, Lochinvar



Accredited for compliance with ISO/IEC 17025-Testing. The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.
 Results provided relate only to the items tested or sampled.


B. Cullen
 Approved Signatory: Brent Cullen
 (Engineering Geologist)
 NATA Accredited Laboratory Number: 18686
 Date of Issue: 23/05/2022

Sample Details

Sample ID: NEW22W-1266-S25
Sampling Method: The results outlined below apply to the sample as received
Material: Clay
Date Sampled: 26/04/2022
Source: On-Site Insitu
Date Submitted: 4/05/2022
Specification: No Specification
Sample Location: BH1611 - (1.00 - 1.15m)
Date Tested: 11/05/2022

Swell Test AS 1289.7.1.1		Shrink Test AS 1289.7.1.1	
Swell on Saturation (%):	1.0	Shrink on drying (%):	3.2
Moisture Content before (%):	29.1	Shrinkage Moisture Content (%):	28.8
Moisture Content after (%):	29.3	Est. inert material (%):	2%
Est. Unc. Comp. Strength before (kPa):	280	Crumbling during shrinkage:	Nil
Est. Unc. Comp. Strength after (kPa):	300	Cracking during shrinkage:	Minor

Shrink Swell



Shrink Swell Index - Iss (%): 2.1

Comments


Report No: SSI:NEW22W-1266-S26

Issue No: 1

Shrink Swell Index Report

Client: McCloy Project Management Pty Ltd
 PO Box 2214
 Dangar NSW 2309

Project No.: NEW17P-0054F
Project Name: Hereford Hill Stage 15 & 16
Project Location: 853 New England Highway, Lochinvar



Accredited for compliance with ISO/IEC 17025-Testing.
 The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.
 Results provided relate only to the items tested or sampled.

B. Cullen
 Approved Signatory: Brent Cullen
 (Engineering Geologist)
 NATA Accredited Laboratory Number: 18686
 Date of Issue: 23/05/2022


Sample Details

Sample ID: NEW22W-1266-S26
Sampling Method: The results outlined below apply to the sample as received
Material: Clay
Source: On-Site Insitu
Specification: No Specification
Sample Location: BH1612 - (0.40 - 0.55m)
Date Tested: 11/05/2022

Date Sampled: 26/04/2022
Date Submitted: 4/05/2022

Swell Test AS 1289.7.1.1		Shrink Test AS 1289.7.1.1	
Swell on Saturation (%):	0.1	Shrink on drying (%):	4.5
Moisture Content before (%):	29.3	Shrinkage Moisture Content (%):	27.7
Moisture Content after (%):	31.3	Est. inert material (%):	3%
Est. Unc. Comp. Strength before (kPa):	250	Crumbling during shrinkage:	Nil
Est. Unc. Comp. Strength after (kPa):	220	Cracking during shrinkage:	Minor

Shrink Swell



Shrink Swell Index - Iss (%): 2.5

Comments

Report No: SSI:NEW22W-1266-S27

Issue No: 1

Shrink Swell Index Report

Client: McCloy Project Management Pty Ltd
 PO Box 2214
 Dangar NSW 2309

Project No.: NEW17P-0054F
Project Name: Hereford Hill Stage 15 & 16
Project Location: 853 New England Highway, Lochinvar




Accredited for compliance with ISO/IEC 17025-Testing.
 The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.
 Results provided relate only to the items tested or sampled.
B. Cullen
 Approved Signatory: Brent Cullen
 (Engineering Geologist)
 NATA Accredited Laboratory Number: 18686
 Date of Issue: 23/05/2022

Sample Details

Sample ID: NEW22W-1266-S27
Sampling Method: The results outlined below apply to the sample as received
Material: Clay
Source: On-Site Insitu
Specification: No Specification
Sample Location: BH1612 - (1.00 - 1.15m)
Date Tested: 11/05/2022
Date Sampled: 26/04/2022
Date Submitted: 4/05/2022

Swell Test AS 1289.7.1.1		Shrink Test AS 1289.7.1.1	
Swell on Saturation (%):	0.4	Shrink on drying (%):	3.8
Moisture Content before (%):	27.8	Shrinkage Moisture Content (%):	27.2
Moisture Content after (%):	30.1	Est. inert material (%):	6%
Est. Unc. Comp. Strength before (kPa):	400	Crumbling during shrinkage:	Nil
Est. Unc. Comp. Strength after (kPa):	250	Cracking during shrinkage:	Nil

Shrink Swell



Shrink Swell Index - Iss (%): 2.2

Comments


Report No: SSI:NEW22W-1266-S28

Issue No: 1

Shrink Swell Index Report

Client: McCloy Project Management Pty Ltd
 PO Box 2214
 Dangar NSW 2309

Project No.: NEW17P-0054F
Project Name: Hereford Hill Stage 15 & 16
Project Location: 853 New England Highway, Lochinvar



Accredited for compliance with ISO/IEC 17025-Testing. The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.
 Results provided relate only to the items tested or sampled.

B. Cullen
 Approved Signatory: Brent Cullen
 (Engineering Geologist)
 NATA Accredited Laboratory Number: 18686
 Date of Issue: 31/05/2022


Sample Details

Sample ID: NEW22W-1266-S28
Sampling Method: The results outlined below apply to the sample as received
Material: Clay
Source: On-Site Insitu
Specification: No Specification
Sample Location: BH1613 - (0.50 - 0.65m)
Date Tested: 13/05/2022

Date Sampled: 26/04/2022
Date Submitted: 4/05/2022

Swell Test AS 1289.7.1.1		Shrink Test AS 1289.7.1.1	
Swell on Saturation (%):	1.9	Shrink on drying (%):	9.2
Moisture Content before (%):	30.1	Shrinkage Moisture Content (%):	31.2
Moisture Content after (%):	37.1	Est. inert material (%):	2%
Est. Unc. Comp. Strength before (kPa):	220	Crumbling during shrinkage:	Nil
Est. Unc. Comp. Strength after (kPa):	150	Cracking during shrinkage:	Minor

Shrink Swell



Shrink Swell Index - Iss (%): 5.6

Comments


Report No: SSI:NEW22W-1266-S29

Issue No: 1

Shrink Swell Index Report

Client: McCloy Project Management Pty Ltd
 PO Box 2214
 Dangar NSW 2309

Project No.: NEW17P-0054F
Project Name: Hereford Hill Stage 15 & 16
Project Location: 853 New England Highway, Lochinvar



Accredited for compliance with ISO/IEC 17025-Testing. The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards. Results provided relate only to the items tested or sampled.

B. Cullen
 Approved Signatory: Brent Cullen
 (Engineering Geologist)
 NATA Accredited Laboratory Number: 18686
 Date of Issue: 31/05/2022


Sample Details

Sample ID: NEW22W-1266-S29
Sampling Method: The results outlined below apply to the sample as received
Material: Clay
Source: On-Site Insitu
Specification: No Specification
Sample Location: BH1613 - (1.00 - 1.15m)
Date Tested: 13/05/2022

Date Sampled: 26/04/2022
Date Submitted: 4/05/2022

Swell Test AS 1289.7.1.1		Shrink Test AS 1289.7.1.1	
Swell on Saturation (%):	2.7	Shrink on drying (%):	7.2
Moisture Content before (%):	34.7	Shrinkage Moisture Content (%):	35.2
Moisture Content after (%):	43.6	Est. inert material (%):	3%
Est. Unc. Comp. Strength before (kPa):	190	Crumbling during shrinkage:	Nil
Est. Unc. Comp. Strength after (kPa):	90	Cracking during shrinkage:	Minor

Shrink Swell



Shrink Swell Index - Iss (%): 4.8

Comments


Report No: SSI:NEW22W-1266-S30

Issue No: 1

Shrink Swell Index Report

Client: McCloy Project Management Pty Ltd
 PO Box 2214
 Dangar NSW 2309

Project No.: NEW17P-0054F
Project Name: Hereford Hill Stage 15 & 16
Project Location: 853 New England Highway, Lochinvar



Accredited for compliance with ISO/IEC 17025-Testing. The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.
 Results provided relate only to the items tested or sampled.

B. Cullen
 Approved Signatory: Brent Cullen
 (Engineering Geologist)
 NATA Accredited Laboratory Number: 18686
 Date of Issue: 23/05/2022


Sample Details

Sample ID: NEW22W-1266-S30
Sampling Method: The results outlined below apply to the sample as received
Material: Clay
Source: On-Site Insitu
Specification: No Specification
Sample Location: BH1614 - (0.70 - 0.95m)
Date Tested: 13/05/2022

Date Sampled: 26/04/2022
Date Submitted: 4/05/2022

Swell Test AS 1289.7.1.1		Shrink Test AS 1289.7.1.1	
Swell on Saturation (%):	0.1	Shrink on drying (%):	6.4
Moisture Content before (%):	26.3	Shrinkage Moisture Content (%):	28.0
Moisture Content after (%):	31.2	Est. inert material (%):	3%
Est. Unc. Comp. Strength before (kPa):	300	Crumbling during shrinkage:	Nil
Est. Unc. Comp. Strength after (kPa):	180	Cracking during shrinkage:	Nil

Shrink Swell



Shrink Swell Index - Iss (%): 3.6

Comments

Report No: SSI:NEW22W-1266-S31

Issue No: 1

Shrink Swell Index Report

Client: McCloy Project Management Pty Ltd
 PO Box 2214
 Dangar NSW 2309

Project No.: NEW17P-0054F
Project Name: Hereford Hill Stage 15 & 16
Project Location: 853 New England Highway, Lochinvar



Accredited for compliance with ISO/IEC 17025-Testing. The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.

Results provided relate only to the items tested or sampled.

B. Cullen


Approved Signatory: Brent Cullen
 (Engineering Geologist)
 NATA Accredited Laboratory Number: 18686
 Date of Issue: 23/05/2022

Sample Details

Sample ID: NEW22W-1266-S31
Sampling Method: The results outlined below apply to the sample as received
Material: Clay
Source: On-Site Insitu
Specification: No Specification
Sample Location: BH1615 - (0.70 - 0.90m)
Date Tested: 13/05/2022
Date Sampled: 26/04/2022
Date Submitted: 4/05/2022

Swell Test AS 1289.7.1.1		Shrink Test AS 1289.7.1.1	
Swell on Saturation (%):	0.8	Shrink on drying (%):	8.4
Moisture Content before (%):	36.8	Shrinkage Moisture Content (%):	37.7
Moisture Content after (%):	41.7	Est. inert material (%):	3%
Est. Unc. Comp. Strength before (kPa):	200	Crumbling during shrinkage:	Nil
Est. Unc. Comp. Strength after (kPa):	90	Cracking during shrinkage:	Moderate

Shrink Swell



Shrink Swell Index - Iss (%): 4.9

Comments


Report No: SSI:NEW22W-1266-S32

Issue No: 1

Shrink Swell Index Report

Client: McCloy Project Management Pty Ltd
 PO Box 2214
 Dangar NSW 2309

Project No.: NEW17P-0054F
Project Name: Hereford Hill Stage 15 & 16
Project Location: 853 New England Highway, Lochinvar



Accredited for compliance with ISO/IEC 17025-Testing. The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.
 Results provided relate only to the items tested or sampled.


B. Cullen
 Approved Signatory: Brent Cullen
 (Engineering Geologist)
 NATA Accredited Laboratory Number: 18686
 Date of Issue: 31/05/2022

Sample Details

Sample ID: NEW22W-1266-S32
Sampling Method: The results outlined below apply to the sample as received
Material: Clay
Date Sampled: 26/04/2022
Source: On-Site Insitu
Date Submitted: 4/05/2022
Specification: No Specification
Sample Location: BH1616 - (0.50 - 0.70m)
Date Tested: 13/05/2022

Swell Test AS 1289.7.1.1		Shrink Test AS 1289.7.1.1	
Swell on Saturation (%):	0.7	Shrink on drying (%):	7.6
Moisture Content before (%):	35.8	Shrinkage Moisture Content (%):	32.8
Moisture Content after (%):	41.6	Est. inert material (%):	1%
Est. Unc. Comp. Strength before (kPa):	240	Crumbling during shrinkage:	Nil
Est. Unc. Comp. Strength after (kPa):	110	Cracking during shrinkage:	Minor

Shrink Swell



Shrink Swell Index - Iss (%): 4.4

Comments


Report No: SSI:NEW22W-1266-S33

Issue No: 1

Shrink Swell Index Report

Client: McCloy Project Management Pty Ltd
 PO Box 2214
 Dangar NSW 2309

Project No.: NEW17P-0054F
Project Name: Hereford Hill Stage 15 & 16
Project Location: 853 New England Highway, Lochinvar



Accredited for compliance with ISO/IEC 17025-Testing. The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.
 Results provided relate only to the items tested or sampled.

B. Cullen
 Approved Signatory: Brent Cullen
 (Engineering Geologist)
 NATA Accredited Laboratory Number: 18686
 Date of Issue: 23/05/2022

Sample Details


Sample ID: NEW22W-1266-S33
Sampling Method: The results outlined below apply to the sample as received
Material: Clay
Source: On-Site Insitu
Specification: No Specification
Sample Location: BH1616 - (1.00 - 1.20m)
Date Tested: 13/05/2022

Date Sampled: 26/04/2022
Date Submitted: 4/05/2022

Swell Test		AS 1289.7.1.1
Swell on Saturation (%):	0.2	
Moisture Content before (%):	32.4	
Moisture Content after (%):	41.1	
Est. Unc. Comp. Strength before (kPa):	240	
Est. Unc. Comp. Strength after (kPa):	90	

Shrink Test		AS 1289.7.1.1
Shrink on drying (%):	8.7	
Shrinkage Moisture Content (%):	34.0	
Est. inert material (%):	2%	
Crumbling during shrinkage:	Nil	
Cracking during shrinkage:	Nil	

Shrink Swell



Shrink Swell Index - Iss (%): 4.9

Comments

APPENDIX C:

CSIRO Sheet BTF 18

**Foundation Maintenance and Footing
Performance: A Homeowner's Guide**

Foundation Maintenance and Footing Performance: A Homeowner's Guide



CSIRO

BTF 18
replaces
Information
Sheet 10/91

Buildings can and often do move. This movement can be up, down, lateral or rotational. The fundamental cause of movement in buildings can usually be related to one or more problems in the foundation soil. It is important for the homeowner to identify the soil type in order to ascertain the measures that should be put in place in order to ensure that problems in the foundation soil can be prevented, thus protecting against building movement.

This Building Technology File is designed to identify causes of soil-related building movement, and to suggest methods of prevention of resultant cracking in buildings.

Soil Types

The types of soils usually present under the topsoil in land zoned for residential buildings can be split into two approximate groups – granular and clay. Quite often, foundation soil is a mixture of both types. The general problems associated with soils having granular content are usually caused by erosion. Clay soils are subject to saturation and swell/shrink problems.

Classifications for a given area can generally be obtained by application to the local authority, but these are sometimes unreliable and if there is doubt, a geotechnical report should be commissioned. As most buildings suffering movement problems are founded on clay soils, there is an emphasis on classification of soils according to the amount of swell and shrinkage they experience with variations of water content. The table below is Table 2.1 from AS 2870, the Residential Slab and Footing Code.

Causes of Movement

Settlement due to construction

There are two types of settlement that occur as a result of construction:

- Immediate settlement occurs when a building is first placed on its foundation soil, as a result of compaction of the soil under the weight of the structure. The cohesive quality of clay soil mitigates against this, but granular (particularly sandy) soil is susceptible.
- Consolidation settlement is a feature of clay soil and may take place because of the expulsion of moisture from the soil or because of the soil's lack of resistance to local compressive or shear stresses. This will usually take place during the first few months after construction, but has been known to take many years in exceptional cases.

These problems are the province of the builder and should be taken into consideration as part of the preparation of the site for construction. Building Technology File 19 (BTF 19) deals with these problems.

Erosion

All soils are prone to erosion, but sandy soil is particularly susceptible to being washed away. Even clay with a sand component of say 10% or more can suffer from erosion.

Saturation

This is particularly a problem in clay soils. Saturation creates a bog-like suspension of the soil that causes it to lose virtually all of its bearing capacity. To a lesser degree, sand is affected by saturation because saturated sand may undergo a reduction in volume – particularly imported sand fill for bedding and blinding layers. However, this usually occurs as immediate settlement and should normally be the province of the builder.

Seasonal swelling and shrinkage of soil

All clays react to the presence of water by slowly absorbing it, making the soil increase in volume (see table below). The degree of increase varies considerably between different clays, as does the degree of decrease during the subsequent drying out caused by fair weather periods. Because of the low absorption and expulsion rate, this phenomenon will not usually be noticeable unless there are prolonged rainy or dry periods, usually of weeks or months, depending on the land and soil characteristics.

The swelling of soil creates an upward force on the footings of the building, and shrinkage creates subsidence that takes away the support needed by the footing to retain equilibrium.

Shear failure

This phenomenon occurs when the foundation soil does not have sufficient strength to support the weight of the footing. There are two major post-construction causes:

- Significant load increase.
- Reduction of lateral support of the soil under the footing due to erosion or excavation.
- In clay soil, shear failure can be caused by saturation of the soil adjacent to or under the footing.

GENERAL DEFINITIONS OF SITE CLASSES

Class	Foundation
A	Most sand and rock sites with little or no ground movement from moisture changes
S	Slightly reactive clay sites with only slight ground movement from moisture changes
M	Moderately reactive clay or silt sites, which can experience moderate ground movement from moisture changes
H	Highly reactive clay sites, which can experience high ground movement from moisture changes
E	Extremely reactive sites, which can experience extreme ground movement from moisture changes
A to P	Filled sites
P	Sites which include soft soils, such as soft clay or silt or loose sands; landslip; mine subsidence; collapsing soils; soils subject to erosion; reactive sites subject to abnormal moisture conditions or sites which cannot be classified otherwise

Tree root growth

Trees and shrubs that are allowed to grow in the vicinity of footings can cause foundation soil movement in two ways:

- Roots that grow under footings may increase in cross-sectional size, exerting upward pressure on footings.
- Roots in the vicinity of footings will absorb much of the moisture in the foundation soil, causing shrinkage or subsidence.

Unevenness of Movement

The types of ground movement described above usually occur unevenly throughout the building's foundation soil. Settlement due to construction tends to be uneven because of:

- Differing compaction of foundation soil prior to construction.
- Differing moisture content of foundation soil prior to construction.

Movement due to non-construction causes is usually more uneven still. Erosion can undermine a footing that traverses the flow or can create the conditions for shear failure by eroding soil adjacent to a footing that runs in the same direction as the flow.

Saturation of clay foundation soil may occur where subfloor walls create a dam that makes water pond. It can also occur wherever there is a source of water near footings in clay soil. This leads to a severe reduction in the strength of the soil which may create local shear failure.

Seasonal swelling and shrinkage of clay soil affects the perimeter of the building first, then gradually spreads to the interior. The swelling process will usually begin at the uphill extreme of the building, or on the weather side where the land is flat. Swelling gradually reaches the interior soil as absorption continues. Shrinkage usually begins where the sun's heat is greatest.

Effects of Uneven Soil Movement on Structures

Erosion and saturation

Erosion removes the support from under footings, tending to create subsidence of the part of the structure under which it occurs. Brickwork walls will resist the stress created by this removal of support by bridging the gap or cantilevering until the bricks or the mortar bedding fail. Older masonry has little resistance. Evidence of failure varies according to circumstances and symptoms may include:

- Step cracking in the mortar beds in the body of the wall or above/below openings such as doors or windows.
- Vertical cracking in the bricks (usually but not necessarily in line with the vertical beds or perpend).

Isolated piers affected by erosion or saturation of foundations will eventually lose contact with the bearers they support and may tilt or fall over. The floors that have lost this support will become bouncy, sometimes rattling ornaments etc.

Seasonal swelling/shrinkage in clay

Swelling foundation soil due to rainy periods first lifts the most exposed extremities of the footing system, then the remainder of the perimeter footings while gradually permeating inside the building footprint to lift internal footings. This swelling first tends to create a dish effect, because the external footings are pushed higher than the internal ones.

The first noticeable symptom may be that the floor appears slightly dished. This is often accompanied by some doors binding on the floor or the door head, together with some cracking of cornice mitres. In buildings with timber flooring supported by bearers and joists, the floor can be bouncy. Externally there may be visible dishing of the hip or ridge lines.

As the moisture absorption process completes its journey to the innermost areas of the building, the internal footings will rise. If the spread of moisture is roughly even, it may be that the symptoms will temporarily disappear, but it is more likely that swelling will be uneven, creating a difference rather than a disappearance in symptoms. In buildings with timber flooring supported by bearers and joists, the isolated piers will rise more easily than the strip footings or piers under walls, creating noticeable doming of flooring.

Trees can cause shrinkage and damage



As the weather pattern changes and the soil begins to dry out, the external footings will be first affected, beginning with the locations where the sun's effect is strongest. This has the effect of lowering the external footings. The doming is accentuated and cracking reduces or disappears where it occurred because of dishing, but other cracks open up. The roof lines may become convex.

Doming and dishing are also affected by weather in other ways. In areas where warm, wet summers and cooler dry winters prevail, water migration tends to be toward the interior and doming will be accentuated, whereas where summers are dry and winters are cold and wet, migration tends to be toward the exterior and the underlying propensity is toward dishing.

Movement caused by tree roots

In general, growing roots will exert an upward pressure on footings, whereas soil subject to drying because of tree or shrub roots will tend to remove support from under footings by inducing shrinkage.

Complications caused by the structure itself

Most forces that the soil causes to be exerted on structures are vertical – i.e. either up or down. However, because these forces are seldom spread evenly around the footings, and because the building resists uneven movement because of its rigidity, forces are exerted from one part of the building to another. The net result of all these forces is usually rotational. This resultant force often complicates the diagnosis because the visible symptoms do not simply reflect the original cause. A common symptom is binding of doors on the vertical member of the frame.

Effects on full masonry structures

Brickwork will resist cracking where it can. It will attempt to span areas that lose support because of subsided foundations or raised points. It is therefore usual to see cracking at weak points, such as openings for windows or doors.

In the event of construction settlement, cracking will usually remain unchanged after the process of settlement has ceased.

With local shear or erosion, cracking will usually continue to develop until the original cause has been remedied, or until the subsidence has completely neutralised the affected portion of footing and the structure has stabilised on other footings that remain effective.

In the case of swell/shrink effects, the brickwork will in some cases return to its original position after completion of a cycle, however it is more likely that the rotational effect will not be exactly reversed, and it is also usual that brickwork will settle in its new position and will resist the forces trying to return it to its original position. This means that in a case where swelling takes place after construction and cracking occurs, the cracking is likely to at least partly remain after the shrink segment of the cycle is complete. Thus, each time the cycle is repeated, the likelihood is that the cracking will become wider until the sections of brickwork become virtually independent.

With repeated cycles, once the cracking is established, if there is no other complication, it is normal for the incidence of cracking to stabilise, as the building has the articulation it needs to cope with the problem. This is by no means always the case, however, and monitoring of cracks in walls and floors should always be treated seriously.

Upheaval caused by growth of tree roots under footings is not a simple vertical shear stress. There is a tendency for the root to also exert lateral forces that attempt to separate sections of brickwork after initial cracking has occurred.

The normal structural arrangement is that the inner leaf of brickwork in the external walls and at least some of the internal walls (depending on the roof type) comprise the load-bearing structure on which any upper floors, ceilings and the roof are supported. In these cases, it is internally visible cracking that should be the main focus of attention, however there are a few examples of dwellings whose external leaf of masonry plays some supporting role, so this should be checked if there is any doubt. In any case, externally visible cracking is important as a guide to stresses on the structure generally, and it should also be remembered that the external walls must be capable of supporting themselves.

Effects on framed structures

Timber or steel framed buildings are less likely to exhibit cracking due to swell/shrink than masonry buildings because of their flexibility. Also, the doming/dishing effects tend to be lower because of the lighter weight of walls. The main risks to framed buildings are encountered because of the isolated pier footings used under walls. Where erosion or saturation cause a footing to fall away, this can double the span which a wall must bridge. This additional stress can create cracking in wall linings, particularly where there is a weak point in the structure caused by a door or window opening. It is, however, unlikely that framed structures will be so stressed as to suffer serious damage without first exhibiting some or all of the above symptoms for a considerable period. The same warning period should apply in the case of upheaval. It should be noted, however, that where framed buildings are supported by strip footings there is only one leaf of brickwork and therefore the externally visible walls are the supporting structure for the building. In this case, the subfloor masonry walls can be expected to behave as full brickwork walls.

Effects on brick veneer structures

Because the load-bearing structure of a brick veneer building is the frame that makes up the interior leaf of the external walls plus perhaps the internal walls, depending on the type of roof, the building can be expected to behave as a framed structure, except that the external masonry will behave in a similar way to the external leaf of a full masonry structure.

Water Service and Drainage

Where a water service pipe, a sewer or stormwater drainage pipe is in the vicinity of a building, a water leak can cause erosion, swelling or saturation of susceptible soil. Even a minuscule leak can be enough to saturate a clay foundation. A leaking tap near a building can have the same effect. In addition, trenches containing pipes can become watercourses even though backfilled, particularly where broken rubble is used as fill. Water that runs along these trenches can be responsible for serious erosion, interstrata seepage into subfloor areas and saturation.

Pipe leakage and trench water flows also encourage tree and shrub roots to the source of water, complicating and exacerbating the problem.

Poor roof plumbing can result in large volumes of rainwater being concentrated in a small area of soil:

- Incorrect falls in roof guttering may result in overflows, as may gutters blocked with leaves etc.

- Corroded guttering or downpipes can spill water to ground.
- Downpipes not positively connected to a proper stormwater collection system will direct a concentration of water to soil that is directly adjacent to footings, sometimes causing large-scale problems such as erosion, saturation and migration of water under the building.

Seriousness of Cracking

In general, most cracking found in masonry walls is a cosmetic nuisance only and can be kept in repair or even ignored. The table below is a reproduction of Table C1 of AS 2870.

AS 2870 also publishes figures relating to cracking in concrete floors, however because wall cracking will usually reach the critical point significantly earlier than cracking in slabs, this table is not reproduced here.

Prevention/Cure

Plumbing

Where building movement is caused by water service, roof plumbing, sewer or stormwater failure, the remedy is to repair the problem. It is prudent, however, to consider also rerouting pipes away from the building where possible, and relocating taps to positions where any leakage will not direct water to the building vicinity. Even where gully traps are present, there is sometimes sufficient spill to create erosion or saturation, particularly in modern installations using smaller diameter PVC fixtures. Indeed, some gully traps are not situated directly under the taps that are installed to charge them, with the result that water from the tap may enter the backfilled trench that houses the sewer piping. If the trench has been poorly backfilled, the water will either pond or flow along the bottom of the trench. As these trenches usually run alongside the footings and can be at a similar depth, it is not hard to see how any water that is thus directed into a trench can easily affect the foundation's ability to support footings or even gain entry to the subfloor area.

Ground drainage

In all soils there is the capacity for water to travel on the surface and below it. Surface water flows can be established by inspection during and after heavy or prolonged rain. If necessary, a grated drain system connected to the stormwater collection system is usually an easy solution.

It is, however, sometimes necessary when attempting to prevent water migration that testing be carried out to establish watertable height and subsoil water flows. This subject is referred to in BTF 19 and may properly be regarded as an area for an expert consultant.


Protection of the building perimeter

It is essential to remember that the soil that affects footings extends well beyond the actual building line. Watering of garden plants, shrubs and trees causes some of the most serious water problems.

For this reason, particularly where problems exist or are likely to occur, it is recommended that an apron of paving be installed around as much of the building perimeter as necessary. This paving

CLASSIFICATION OF DAMAGE WITH REFERENCE TO WALLS

Description of typical damage and required repair	Approximate crack width limit (see Note 3)	Damage category
Hairline cracks	<0.1 mm	0
Fine cracks which do not need repair	<1 mm	1
Cracks noticeable but easily filled. Doors and windows stick slightly	<5 mm	2
Cracks can be repaired and possibly a small amount of wall will need to be replaced. Doors and windows stick. Service pipes can fracture. Weathertightness often impaired	5–15 mm (or a number of cracks 3 mm or more in one group)	3
Extensive repair work involving breaking-out and replacing sections of walls, especially over doors and windows. Window and door frames distort. Walls lean or bulge noticeably, some loss of bearing in beams. Service pipes disrupted	15–25 mm but also depend on number of cracks	4



- Water that is transmitted into masonry, metal or timber building elements causes damage and/or decay to those elements.
- High subfloor humidity and moisture content create an ideal environment for various pests, including termites and spiders.
- Where high moisture levels are transmitted to the flooring and walls, an increase in the dust mite count can ensue within the living areas. Dust mites, as well as dampness in general, can be a health hazard to inhabitants, particularly those who are abnormally susceptible to respiratory ailments.

The garden

The ideal vegetation layout is to have lawn or plants that require only light watering immediately adjacent to the drainage or paving edge, then more demanding plants, shrubs and trees spread out in that order.

Overwatering due to misuse of automatic watering systems is a common cause of saturation and water migration under footings. If it is necessary to use these systems, it is important to remove garden beds to a completely safe distance from buildings.

Existing trees

Where a tree is causing a problem of soil drying or there is the existence or threat of upheaval of footings, if the offending roots are subsidiary and their removal will not significantly damage the tree, they should be severed and a concrete or metal barrier placed vertically in the soil to prevent future root growth in the direction of the building. If it is not possible to remove the relevant roots without damage to the tree, an application to remove the tree should be made to the local authority. A prudent plan is to transplant likely offenders before they become a problem.

Information on trees, plants and shrubs

State departments overseeing agriculture can give information regarding root patterns, volume of water needed and safe distance from buildings of most species. Botanic gardens are also sources of information. For information on plant roots and drains, see Building Technology File 17.

Excavation

Excavation around footings must be properly engineered. Soil supporting footings can only be safely excavated at an angle that allows the soil under the footing to remain stable. This angle is called the angle of repose (or friction) and varies significantly between soil types and conditions. Removal of soil within the angle of repose will cause subsidence.

Remediation

Where erosion has occurred that has washed away soil adjacent to footings, soil of the same classification should be introduced and compacted to the same density. Where footings have been undermined, augmentation or other specialist work may be required. Remediation of footings and foundations is generally the realm of a specialist consultant.

Where isolated footings rise and fall because of swell/shrink effect, the homeowner may be tempted to alleviate floor bounce by filling the gap that has appeared between the bearer and the pier with blocking. The danger here is that when the next swell segment of the cycle occurs, the extra blocking will push the floor up into an accentuated dome and may also cause local shear failure in the soil. If it is necessary to use blocking, it should be by a pair of fine wedges and monitoring should be carried out fortnightly.

This BTF was prepared by John Lewer FAIB, MIAMA, Partner, Construction Diagnosis.

should extend outwards a minimum of 900 mm (more in highly reactive soil) and should have a minimum fall away from the building of 1:60. The finished paving should be no less than 100 mm below brick vent bases.

It is prudent to relocate drainage pipes away from this paving, if possible, to avoid complications from future leakage. If this is not practical, earthenware pipes should be replaced by PVC and backfilling should be of the same soil type as the surrounding soil and compacted to the same density.

Except in areas where freezing of water is an issue, it is wise to remove taps in the building area and relocate them well away from the building – preferably not uphill from it (see BTF 19).

It may be desirable to install a grated drain at the outside edge of the paving on the uphill side of the building. If subsoil drainage is needed this can be installed under the surface drain.

Condensation

In buildings with a subfloor void such as where bearers and joists support flooring, insufficient ventilation creates ideal conditions for condensation, particularly where there is little clearance between the floor and the ground. Condensation adds to the moisture already present in the subfloor and significantly slows the process of drying out. Installation of an adequate subfloor ventilation system, either natural or mechanical, is desirable.

Warning: Although this Building Technology File deals with cracking in buildings, it should be said that subfloor moisture can result in the development of other problems, notably:

The information in this and other issues in the series was derived from various sources and was believed to be correct when published.

The information is advisory. It is provided in good faith and not claimed to be an exhaustive treatment of the relevant subject.

Further professional advice needs to be obtained before taking any action based on the information provided.

Distributed by

CSIRO PUBLISHING PO Box 1139, Collingwood 3066, Australia

Freecall 1800 645 051 Tel (03) 9662 7666 Fax (03) 9662 7555 www.publish.csiro.au

Email: publishing.sales@csiro.au

© CSIRO 2003. Unauthorised copying of this Building Technology file is prohibited